

## UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG ☒ ELECTRIC LOGS ☒ WATER SANDS ☒ LOCATION INSPECTED ☒ SUB. REPORT/abd.

DATE FILED JULY 31, 1998  
LAND: FEE & PATENTED STATE LEASE NO. PUBLIC LEASE NO. UTU-76241 INDIAN  
DRILLING APPROVED: AUGUST 10, 1998  
SPUDDED IN:  
COMPLETED: PUT TO PRODUCING:  
INITIAL PRODUCTION:  
GRAVITY A.P.I.  
GOR:  
PRODUCING ZONES:  
TOTAL DEPTH:  
WELL ELEVATION:  
DATE ABANDONED:  
FIELD: MONUMENT BUTTE  
UNIT: GREATER BOUNDARY  
COUNTY: DUCHESNE  
WELL NO. TAR SANDS FEDERAL #15-28-8-17 API NO. 43-013-32109  
LOCATION 518 FSL FT. FROM (N) (S) LINE. 1899 FEL FT. FROM (E) (W) LINE. SW SE 1/4 - 1/4 SEC. 28


TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
8S	17E	28	INLAND PRODUCTION				

**UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT**

**APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK**

1a. TYPE OF WORK <b>DRILL</b> <input checked="" type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. <b>U-76241</b>	
1b. TYPE OF WELL <b>OIL</b> <input type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>OTHER</b> <input type="checkbox"/> <b>SINGLE</b> <input type="checkbox"/> <b>MULTIPLE</b> <input type="checkbox"/> <b>WELL</b> <input checked="" type="checkbox"/> <b>WELL</b> <input type="checkbox"/> <b>OTHER</b> <input type="checkbox"/> <b>ZONE</b> <input type="checkbox"/> <b>ZONE</b> <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR <b>Inland Production Company</b>		7. UNIT AGREEMENT NAME <b>Greater Boundary Unit</b>	
3. ADDRESS OF OPERATOR <b>P.O. Box 790233 Vernal, UT 84079</b> <b>Phone: (801) 789-1866</b>		8. FARM OR LEASE NAME <b>Tar Sands Federal</b>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At Surface <b>SW/SE</b> At proposed Prod. Zone <b>517.5' FSL &amp; 1898.9' FEL</b> <i>159 679</i>		9. WELL NO. <b>#15-28-8-17</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* <b>13.1 miles southeast of Myton, Utah</b>		10. FIELD AND POOL OR WILDCAT <b>Monument Butte</b>	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) <b>517.5'</b>	16. NO. OF ACRES IN LEASE <b>1880</b>	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA <b>Sec. 28, T8S, R17E</b>	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.	19. PROPOSED DEPTH <b>6500'</b>	12. County <b>Duchesne</b>	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) <b>5132.4' GR</b>		13. STATE <b>UT</b>	
22. APPROX. DATE WORK WILL START* <b>4th Quarter 1998</b>			
23. <b>PROPOSED CASING AND CEMENTING PROGRAM</b>			
SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH
<b>Refer to Monument Butte Field SOP's Drilling Program/Casing Design</b>			

The Conditions of Approval For Application For Permit To Drill are attached.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone.

If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED *Cheryl Cameron* TITLE **Regulatory Specialist** DATE **7/23/98**  
**Cheryl Cameron**

(This space for Federal or State office use)

PERMIT NO. **43-013-32109** APPROVAL DATE \_\_\_\_\_

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY: **Federal Approval of this Action is Necessary**

APPROVED BY *Bradley G. Hill* TITLE **BRADLEY G. HILL  
RECLAMATION SPECIALIST III** DATE **8/10/98**

**\*See Instructions On Reverse Side**


Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*584571.2  
4437252.7*

**T8S, R17E, S.L.B.&M.**

**INLAND PRODUCTION CO.**

WELL LOCATION, TAR SANDS FED #15-28-8-17,  
LOCATED AS SHOWN IN THE SW 1/4 SE 1/4 OF  
SECTION 28, T8S, R17E, S.L.B.&M. DUCHESNE  
COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. GENE

STEWART  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 144102  
STATE OF UTAH

**TRI STATE LAND SURVEYING & CONSULTING**

38 WEST 100 NORTH - VERNAL, UTAH 84078  
(801) 781-2501

SCALE: 1" = 1000'

SURVEYED BY: DS CS

DATE: 7-15-98

WEATHER: HOT

NOTES:

FILE #


◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)



July 29, 1998

Bureau of Land Management  
Vernal District Office  
170 South 500 East  
Vernal, Utah 84078



**ATTENTION: Ed Forsman/Wayne Bankert**


**RE: Tar Sands Federal #15-28-8-17  
Monument Butte Federal #4-24-8-16  
Monument Butte Federal #1-23-8-16  
Monument Butte Federal #3-23-8-16  
Monument Butte Federal #8-23-8-16  
S. Wells Draw #10-4-9-16  
S. Wells Draw #14A-4-9-16  
S. Wells Draw #16-4-9-16  
S. Wells Draw #5-3-9-16  
S. Wells Draw #12-3-9-16**

**Tar Sands Federal #16-28-8-17  
Monument Butte Federal #5-24-8-16  
Monument Butte Federal #2-23-8-16  
Monument Butte Federal #7-23-8-16  
S. Wells Draw #9-4-9-16  
S. Wells Draw #11-4-9-16  
S. Wells Draw #15-4-9-16  
S. Wells Draw #4-3-9-16  
S. Wells Draw #13-3-9-16**

Gentlemen:

Enclosed is the original and two copies (each) of Application For Permit To Drill, for the above referenced locations.

Please do not hesitate to contact me in the Vernal Branch Office, if you need additional Information, or have questions.

Sincerely,  
  
Cheryl Cameron  
Regulatory Specialist

cc: State of Utah  
Division of Oil, Gas & Mining  
P.O. Box 145801  
1594 West North Temple, Suite 1210  
Salt Lake City, Utah 84114-5801

**INLAND PRODUCTION COMPANY  
TAR SANDS FEDERAL #15-28-8-17  
SE/SE SECTION 28, T8S, R17E  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**DRILLING PROGRAM**

**1. GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

**2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1690'
Green River	1690'
Wasatch	6500'

**3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1690' – 6500' - Oil

**4. PROPOSED CASING PROGRAM**

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

**5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

Please refer to the Monument Butte Field SOP. See Exhibit "F".

**6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

Please refer to the Monument Butte Field SOP.

**7. AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Please refer to the Monument Butte Field SOP.

**8. TESTING, LOGGING AND CORING PROGRAMS:**

Please refer to the Monument Butte Field SOP.

**9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

The anticipated maximum bottom hole pressure is 1800 psi. It is not anticipated that abnormal temperatures will be encountered; nor that any other abnormal hazards such as H<sub>2</sub>S will be encountered in this area.

**10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

Please refer to the Monument Butte Field SOP

**INLAND PRODUCTION COMPANY  
TAR SANDS FEDERAL #15-28-8-17  
SW/SE SECTION 28, T8S, R17E  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**1. EXISTING ROADS**

See attached Topographic Map "A"

To reach Inland Production Company well location site Tar Sands Federal #15-28-8-17 located in the SW 1/4 SE 1/4 Section 28, T8S, R17E, S.L.B. 7 M. Duchesne County, Utah:

Proceed westerly out of Myton, Utah along Highway 40 - 1.6 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southerly along this road 9.9 miles  $\pm$  to its junction with a dirt road to the northeast; continue northeasterly 1.6 miles to the beginning of the proposed access road.

**2. PLANNED ACCESS ROAD**

See Topographic Map "B" for the location of the proposed access road.

**3. LOCATION OF EXISTING WELLS**

Refer to Exhibit "D".

**4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

**5. LOCATION AND TYPE OF WATER SUPPLY**

Please refer to the Monument Butte Field SOP. See Exhibit "C".

**6. SOURCE OF CONSTRUCTION MATERIALS**

Please refer to the Monument Butte Field SOP.

**7. METHODS FOR HANDLING WASTE DISPOSAL**

Please refer to the Monument Butte Field SOP. See Exhibit "E".

**8. ANCILLARY FACILITIES**

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s). Refer to Exhibit "E".

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management

12. **OTHER ADDITIONAL INFORMATION** *Archaeological Survey & Pipeline ROW*

The Archaeological Cultural Resource Survey Report is attached.

Inland Production Company requests that a pipeline ROW be granted to the Tar Sands Federal #15-28-8-17 for a 3" – 4" poly fuel gas line and a 4" – 6" poly gas gathering line. Both lines will tie-in to the existing pipeline. Inland requests that a 30' width for the ROW and an additional 30' width for working surface as necessary. Refer to Topographic map "B".

13. **LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION**

*Representative*

Name: Cheryl Cameron  
Address: P.O. Box 790233 Vernal, Utah 84079  
Telephone: (435) 789-1866


*Certification*


Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #15-28-8-17 SW/SE Section 28, Township 8S, Range 17E: Lease U-76241 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488914.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.


7/23/98

Date

  
Cheryl Cameron  
Regulatory Specialist




**TAR SANDS FED. #15-28-8-17**  
**SEC. 28, T8S, R17E, S.L.B.&M.**  
**TOPO MAP "A"**




*Tri-State*  
*Land Surveying Inc.*  
 (801) 781-2501  
 38 WEST 100 NORTH VERNAL, UTAH 84078







**TAR SANDS FEDERAL #15-28-8-17**  
**SEC. 28, T8S, R17E, S.L.B.&M.**  
**TOPO MAP "B"**



SCALE 1" = 1000'



# EXHIBIT "C"



**Inland**  
 475 17<sup>th</sup> Street Suite 1500  
 Denver, Colorado 80202  
 Phone: (303) 292-0900

**Regional Area**


Duchesne County, Utah

Date: 4/18/97 J.A.



# INLAND PRODUCTION COMPANY

TAR SANDS FED. #15-28-8-17  
SECTION 28, T8S, R17E, S.L.B.&M.



## REFERENCE POINTS

170' NORTH = 5137.1'  
220' NORTH = 5137.8'  
195' EAST = 5133.5'  
245' EAST = 5316.5'

SURVEYED BY: DS CS

DRAWN BY: NBW





DATE: 7-15-98

SCALE: 1" = 50'

FILE

**Tri State**  
Land Surveying, Inc.  
(435) 781-2501  
38 WEST 100 NORTH VERNAL, UTAH 84078

## CROSS SECTIONS

**TAR SANDS FED #15-28-8-17**APPROXIMATE YARDAGES

CUT = 3,986 Cu. Yds.

FILL = 60 Cu. Yds.

PIT = 560 Cu. Yds.

6" TOPSOIL = 1030 Cu. Yds.

**Tri State**  
*Land Surveying, Inc.*  
 (435) 781-2501  
 38 WEST 100 NORTH, VERNAL, UTAH 84078

Well No.: Tar Sands 15-28-8-17

CONDITIONS OF APPROVAL  
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Inland Production Company

Well Name & Number: Tar Sands 15-28-8-17

API Number:

Lease Number: UTU-76241

Location: SWSE Sec. 28, T8S, R17E

**GENERAL**

Access pad from W, along existing gas line Right-of-way.

**CULTURAL RESOURCES**

See *CONDITIONS OF APPROVAL FOR INLAND RESOURCES MONUMENT BUTTE-MYTON BENCH WATERFLOOD ENVIRONMENTAL ASSESSMENT DUCHESNE AND UINTAH COUNTIES, UTAH EA NUMBER 1996-61.*

**PALEONTOLOGICAL RESOURCES**

See *CONDITIONS OF APPROVAL FOR INLAND RESOURCES MONUMENT BUTTE-MYTON BENCH WATERFLOOD ENVIRONMENTAL ASSESSMENT DUCHESNE AND UINTAH COUNTIES, UTAH EA NUMBER 1996-61.*

**SOILS, WATERSHEDS, AND FLOODPLAINS**

See *CONDITIONS OF APPROVAL FOR INLAND RESOURCES MONUMENT BUTTE-MYTON BENCH WATERFLOOD ENVIRONMENTAL ASSESSMENT DUCHESNE AND UINTAH COUNTIES, UTAH EA NUMBER 1996-61.*

**WILDLIFE AND FISHERIES**

See *CONDITIONS OF APPROVAL FOR INLAND RESOURCES MONUMENT BUTTE-MYTON BENCH WATERFLOOD ENVIRONMENTAL ASSESSMENT DUCHESNE AND UINTAH COUNTIES, UTAH EA NUMBER 1996-61.*

**THREATENED, ENDANGERED, AND OTHER SENSITIVE SPECIES**

See *CONDITIONS OF APPROVAL FOR INLAND RESOURCES MONUMENT BUTTE-MYTON BENCH WATERFLOOD ENVIRONMENTAL ASSESSMENT DUCHESNE AND UINTAH COUNTIES, UTAH EA NUMBER 1996-61.*

**FERRUGINOUS HAWK:** In the event that this well becomes a producing well, it must be equipped with a multi-cylinder engine or hospital muffler to reduce noise levels.

**MOUNTAIN PLOVER:** If new construction or surface disturbing activities are scheduled to occur between March 15 and August 15, detailed surveys of the area within 0.5 mile of the proposed location and within 300 feet of proposed access routes must be conducted to detect the presence of mountain plovers. All surveys must be completed prior to initiating new construction or surface disturbing activities (see Survey Protocol COAs EA Number 1996-61).

#### **OTHER**

WORKSHEET  
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 07/31/98

API NO. ASSIGNED: 43-013-32109

WELL NAME: TAR SANDS 15-28-8-17  
OPERATOR: INLAND PRODUCTION COMPANY (N5160)  
CONTACT: Cheryl Cameron (435) 789-1866

PROPOSED LOCATION:  
SWSE 28 - T08S - R17E  
SURFACE: 0518-FSL-1899-FEL  
BOTTOM: 0518-FSL-1899-FEL  
DUCHESNE COUNTY  
MONUMENT BUTTE FIELD (105)

LEASE TYPE: FED  
LEASE NUMBER: U-76241  
SURFACE OWNER: Federal

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

PROPOSED FORMATION: GRRV

RECEIVED AND/OR REVIEWED:

☒ Plat  
☒ Bond: Federal ☒ State ☐ Fee ☐  
(No. 4488944)  
☒ Potash (Y/N)  
☒ Oil Shale (Y/N) \*190-5(B)  
☒ Water Permit  
(No. Goshute Water District)  
☒ RDCC Review (Y/N)  
(Date: \_\_\_\_\_)  
☒ St/Fee Surf Agreement (Y/N)


LOCATION AND SITING:

☒ R649-2-3. Unit Greater Boundary  
☐ R649-3-2. General  
☐ R649-3-3. Exception  
☐ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Date: \_\_\_\_\_

COMMENTS: \*Not listed in 1998 Unit P.O.D. (BLM added 8-5-98)

STIPULATIONS: ① FEDERAL APPROVAL






DIVISION OF OIL, GAS & MINING

OPERATOR: INLAND PRODUCTION COMPANY (N5160)

FIELD: MONUMENT BUTTE (105)

SEC. 28 TWP 8S, RNG 17E

COUNTY: DUCHESNE UAC: R649-3-2 STATEWIDE SPACING




DATE PREPARED:  
3-AUG-1998

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:  
3160  
(UT-922)



Memorandum

To: Assistant District Manager Minerals, Vernal District  
From: Michael Coulthard, Petroleum Engineer  
Subject: 1998 Plan of Development Greater Boundary  
Unit Duchesne County, Utah.

Pursuant to email between Lisha Cordova, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management. The following wells are planned for calendar year 1998 within the Greater Boundary Unit, Duchesne County, Utah.

API #	WELL NAME	LOCATION
43-013-32109	TAR SANDS 15-28-8-17	0518-FSL-1899-FEL 28 08S 17E
43-013-32111	TAR SANDS 16-28-8-17	0614-FSL-0515-FEL 28 08S 17E

This office has no objection to permitting the well at this time.

/s/ Michael L. Coulthard

bcc: File - Grearter Boundary  
Division of Oil Gas and Mining  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:--



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

Michael O. Leavitt  
Governor

Lowell P. Braxton  
Division Director

August 10, 1998

Inland Production Company  
P.O. Box 790233  
Vernal, Utah 84079

Re: Tar Sands Federal 15-28-8-17 Well, 518' FSL, 1899' FEL,  
SW SE, Sec. 28, T. 8 S., R. 17 E., Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-32109.

Sincerely,

for John R. Baza  
Associate Director

lwp

Enclosures

cc: Duchesne County Assessor  
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company  
Well Name & Number: Tar Sand Federal 15-28-8-17  
API Number: 43-013-32109  
Lease: U-76241  
Location: SW SE Sec. 28 T. 8 S. R. 17 E.

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours prior to spudding the well. Contact Jim Thompson at (801) 538-5336.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Dan Jarvis at (801) 538-5338 or Robert Krueger at (801) 538-5274.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.


4. State approval of this well does not supersede the required federal approval which must be obtained prior to drilling.

**UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT**

**APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK**

1a. TYPE OF WORK <b>DRILL</b> <input checked="" type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. <b>U-76241</b>	
1b. TYPE OF WELL <b>OIL</b> <input checked="" type="checkbox"/> <b>GAS</b> <input type="checkbox"/> <b>SINGLE</b> <input type="checkbox"/> <b>MULTIPLE</b> <input type="checkbox"/> <b>WELL</b> <input checked="" type="checkbox"/> <b>WELL</b> <input type="checkbox"/> <b>OTHER</b> <input type="checkbox"/> <b>ZONE</b> <input type="checkbox"/> <b>ZONE</b> <input type="checkbox"/>		6. IF INDIAN, ALOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR <b>Inland Production Company</b>		7. UNIT AGREEMENT NAME <b>Greater Boundary Unit</b>	
3. ADDRESS OF OPERATOR <b>P.O. Box 790233 Vernal, UT 84079</b> <b>Phone: (801) 789-1866</b>		8. FARM OR LEASE NAME <b>Tar Sands Federal</b>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)* At Surface <b>SW/SE</b> At proposed Prod. Zone <b>517.5' FSL &amp; 1898.9' FEL</b>		9. WELL NO. <b>#15-28-8-17</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* <b>13.1 miles southeast of Myton, Utah</b>		10. FIELD AND POOL OR WILDCAT <b>Monument Butte</b>	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) <b>517.5'</b>	16. NO. OF ACRES IN LEASE <b>1880</b>	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA <b>Sec. 28, T8S, R17E</b>	
18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.	19. PROPOSED DEPTH <b>6500'</b>	12. County <b>Duchesne</b>	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) <b>5132.4' GR</b>		13. STATE <b>UT</b>	
22. APPROX. DATE WORK WILL START* <b>4th Quarter 1998</b>		20. ROTARY OR CABLE TOOLS <b>Rotary</b>	
23. PROPOSED CASING AND CEMENTING PROGRAM			
SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH
<b>Refer to Monument Butte Field SOP's Drilling Program/Casing Design</b>			
QUANTITY OF CEMENT			

The Conditions of Approval For Application For Permit To Drill are attached.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present pr  
If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical de

24. SIGNED Cheryl Cameron TITLE Regulatory Specialist DATE 7/23/98  
**Cheryl Cameron**

(This space for Federal or State office use)

PERMIT NO. \_\_\_\_\_ APPROVAL DATE \_\_\_\_\_

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.


CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE Assistant Field Manager DATE 10/15/1998  
**Mineral Resources**

**\*See Instructions On Reverse Side**

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

NOTICE OF APPROVAL CONDITIONS OF APPROVAL ATTACHED



CONDITIONS OF APPROVAL  
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Inland Production Company

Well Name & Number: Tar Sands Federal 15-28-8-17

API Number: 43-013-32109

Lease Number: U -76241

Location: NWSE Sec. 28 T. 8S R. 17E

Agreement Name: Greater Boundary Unit

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

### CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

#### A. DRILLING PROGRAM

##### 1. Casing Program and Auxiliary Equipment

As a minimum, the usable water resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the shallowest potential productive zone.

### SURFACE USE PROGRAM

#### Location Reclamation

The following seed mixture will be used on the stock piled topsoil, reclamation of the reserve pit and for final reclamation: (All poundages are in Pure Live Seed)

nuttals saltbush	Atriplex nuttalli v. cuneata	3 lbs/acre
shadscale	Atriplex confertifolia	3 lbs/acre
fourwing saltbush	Atriplex canescens	4 lbs/acre
squirreltail	Sitanion hystix	2 lbs/acre

The location topsoil pile shall be seeded immediately after site construction by broadcasting the seed, then walking the topsoil pile with the dozer to plant the seed.

The reserve pit shall have a small amount of topsoil stock piled near by to be used to spread over the reserve pit area at the time the reserve pit is reclaimed.

At the time of final abandonment the location and access will be recontoured to natural topography and topsoil spread over the area and the surface seeded immediately. If the previously reclaimed surface of the reserve pit needs additional contouring, the topsoil over the pit will be scraped off and then used as additional topsoil for final reclamation.

#### Wildlife Habitat

If the location is to be Constructed or Drilled 2/1 to 8/15 additional surveys for golden eagle, ferruginous hawk and mountain plover will be required before development can occur.

**Hookless Cactus Habitat**

Due to the presence of the Hookless Cactus; at the time of development for the access road and well location the dirt contractor performing the development will meet with the authorized officer of the BLM on location. This is to assure that the dirt workers are aware of the need to remain on approved areas for construction and avoid habitat that may have cactus plants. All construction work will be south of the existing east west surface gas line.



**INLAND PRODUCTION COMPANY**  
**GEOLOGIC PROGNOSIS AND LOG DISTRIBUTION LIST**  
(updated 6/9/2000)

**WELL:** Tar Sands Federal #15-28-8-17

**API Number:** 43-013-32109

**LOCATION:** 518' FSL, 1899' FEL (SWSE)  
Section 28, T8S, R17E  
Duchesne County, Utah

**ELEVATION:** 5132' Ground  
5142' KB

**TOPS:**

Uinta Formation	surface
Green River Formation	
Garden Gulch Member	
Point Three Marker	4519'
'X' Marker	4744'
'Y' Marker	4777'
Douglas Creek Member	4906'
Bicarbonate	5146'
B Limestone	5325'
Castle Peak Limestone	5749'
Basal Limestones	

**ANTICIPATED PAY SANDS:**

GB-6	4499'
C-SD	5078'
B-0.5	5182'
B-2	5291'
CP-0.5	5765'
CP-1	5793'
CP-2	5826'
CP-3	5909'

**TOTAL DEPTH:** 6050'

**CORES:** None planned

**DSTS:** None planned

**SAMPLES:** None planned

**DRILLING:**

Union Rig#14: (435) 828 6434

Pusher: (435) 828 6433 Rex Harris

Superintendent: David Gray (435) 828 8031 (cellular)

**REPORT WATER FLOWS TO UTAH DIVISION OF OIL, GAS AND MINING:** (801) 538 5340

**OPEN HOLE LOGGING:**

Phoenix Surveys: David Jull (435) 637 4420

DIGL/SP/GR Suite: TD to surface casing

CDL/CNL/GR/CAL Suite logs: TD to 3000'

Gamma Ray scale 0-150

Matrix density 2.68

LAS data floppy required.

**DATA DISTRIBUTION:**

**RECEIVED**

JUL 31 2000

**DIVISION OF  
OIL, GAS AND MINING**

Inland Production Company (Mail 6 copies)  
Route #3 Box 3630  
Myton, UT 84052  
Attn: Brad Mecham

Inland Production Company (Mail 6 copies,  
EXPRESS)  
410 17th St., Suite 700  
Denver, CO 80202  
Fax: 303-382-4455  
Attn: Josh Axelson

State of Utah  
Division of Oil, Gas and Mining (Mail 1 copy)  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

Bureau of Land Management (Mail 1 copy)  
170 S. 500 East  
Vernal, UT 84078  
Attn: Ed Forsman

**COMPANY CONTACTS:**

**Pat Wisener** (District Drilling Foreman)  
(435) 646 3721 office  
(435) 646 3031 office fax  
(435) 823 7468 cellular  
(435) 646 1270 pager

**Brad Mecham** (District Manager)  
(435) 646 3721 office  
(435) 646 3031 office fax  
(435) 823 6205 cellular  
(435) 353 4211 home

**Donn Murphy** (Operations Manager)  
(303) 893 0102 X440 office  
(303) 526 7748 home  
(435) 823 3737 cellular

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: INLAND PRODUCTION COMPANY

Well Name: TAR SANDS 15-28-8-17

Api No. 43-013-32109 LEASE TYPE: FEDERAL

Section 28 Township 08S Range 17E County DUCHESNE

Drilling Contractor UNION DRILLING RIG # 14

SPUDDED:

Date 08/10/2000

Time 8:15 PM

How DRY

Drilling will commence \_\_\_\_\_

Reported by PAT WISENER

Telephone # 1-435-823-7468

Date 08/11/2000 Signed: CHD

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.  
Use "APPLICATION FOR PERMIT -" for such proposals

**SUBMIT IN TRIPLICATE**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

**INLAND PRODUCTION COMPANY**

3. Address and Telephone No.

**Route 3 Box 3630 Myton, Utah 84052 435-646-3721**

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

**517.5'FSL & 1898.91'FEL SW/SE  
Sec.28, T8S, R17E**

5. Lease Designation and Serial No.

**U-76241**

6. If Indian, Allottee or Tribe Name

**NA**

7. If Unit or CA, Agreement Designation

**Greater Boundry**

8. Well Name and No.

**Tar Sands 15-28-8-17**

9. API Well No.

**43-013-32109**

10. Field and Pool, or Exploratory Area

**MONUMENT BUTTE**

11. County or Parish, State

**Duchesne County, UTAH**

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Surface Spud**

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

MIRU UNION RIG # 14. Set equipment on 8/7/00. Repair equipment. Drill mouse hole & rat hole. Spud well @ 8:15pm on 8/10/00. Drill 17 1/4" hole and set 23' of 133/8" conductor. Nipple up cellar. Drill 12 1/4" hole with air mist to a depth of 325". TIH w/ 85/8" J-55 csg. Landed @ 307.16' KB. Cement with \*141sks class "G" w/ 2% CaCL2 & 1/4#/sk Cello-flake mixed @ 15.8ppg.>1.17 YLD. Estimated 4 bbls cement to surface. WOC 4 hours. Break out & Nipple up BOP's. Pressure test Kelly, TIW, Choke manifold, & BOP's TO 2000 psi. Test 85/8" CSG to 1500 PSI. ALL TESTED GOOD. Vernal District BLM & Utah DOGM notified by phone. Drill 77/8" hole with water mist to a depth of 2230'.

RECEIVED

7/23/00

DIVISION OF  
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct

Signed

*Pat W. Zene*

Title

**Drilling Foreman**

Date

**08/14/2000**

(This space for Federal or State office use)

Approved by

Title

**Accepted by the  
Utah Division of  
Oil, Gas & Mining**

Date

Conditions of approval, if any:

**CC: UTAH DOGM**

# INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8" CASING SET AT 307.16

LAST CASING 8 5/8" SET AT 307.16/KB  
 DATUM 10' KB  
 DATUM TO CUT OFF CASING \_\_\_\_\_  
 DATUM TO BRADENHEAD FLANGE \_\_\_\_\_  
 TD DRILLER 325' LOGGER \_\_\_\_\_  
 HOLE SIZE 12 1/4"

OPERATOR INLAND PRODUCTION COMPANY  
 WELL Tars Sands 15-28-8-17  
 FIELD/PROSPECT Monument Butte  
 CONTRACTOR & RIG # UNION RIG 14

## LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		LANDING JT					14
		WHI " 92 " CSG HEAD			8rd	A	0.95
7	8 5/8"	Maverick SC&T CSG	24 #	J-55	8rd	A	295.31
		SHOE - <b>GUIDE</b>			8rd	A	0.9

CASING INVENTORY BAL.	FEET	JTS	TOTAL LENGTH OF STRING	311.16
TOTAL LENGTH OF STRING	311.16	7	LESS CUT OFF PIECE	14
LESS NON CSG. ITEMS	15.85		PLUS DATUM TO T/CUT OFF CSG	10
PLUS FULL JTS. LEFT OUT	0	0	CASING SET DEPTH	<b>307.16'</b>
TOTAL	295.31	7		

TOTAL CSG. DEL. (W/O THRDS)	295.31	7	} COMPARE	
TIMING	1ST STAGE			
BEGIN RUN CSG.	9:30am		GOOD CIRC THRU JOB	YES
CSG. IN HOLE	10:15am		Bbls CMT CIRC TO SURFACE	4 bbls
BEGIN CIRC	10:24am	10:30am	RECIPROCATED PIPE FOR	THRU FT STROKE
BEGIN PUMP CMT	10:36am		DID BACK PRES. VALVE HOLD ?	N/A
BEGIN DSPL. CMT	10:44am		BUMPED PLUG TO	220 PSI
PLUG DOWN		11:00am		

CEMENT USED	CEMENT COMPANY- <b>B. J.</b>		
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	141	Class "G" w/ 2% CaCL2 + .1/4# /sk. Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield	

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
1 on middle of first JT, 1 on collar of the second & third JT. TOTAL 3	

COMPANY REPRESENTATIVE Pat Wisener

DATE 08/11/2000

P. 02/02

FAX NO. 435 846 3031

INLAND PRODUCTION CO

AUG-18-00 FRI 03:22 PM

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING  
ENTITY ACTION FORM - FORM 6

OPERATOR: INLAND PRODUCTION COMPANY  
ADDRESS: RT. 3 BOX 3630  
MYTON, UT 84052

OPERATOR ACCT. NO. NS160


ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
<u>8</u> <u>A</u>	<u>99999</u>	<u>12391</u>	<u>43-013-32109</u>	<u>Tar Sands Federal #15-28</u>	<u>SW/SE</u>	<u>28</u>	<u>8S</u>	<u>17E</u>	<u>Duchesne</u>	<u>August 10, 2000</u>	<u>8/10/2000</u>
WELL 1 COMMENTS: <u>8-21-00</u>											
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
WELL 2 COMMENTS:											
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
WELL 3 COMMENTS:											
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
WELL 4 COMMENTS:											
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Schedule new entry for new well (single well entry)
- B - Add new well to existing entry (group or unit well)
- C - Reassign well from one existing entry to another existing entry
- D - Reassign well from one existing entry to a new entry
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

(355)

  
Signature Kobbie S. Jones  
Production Clerk  
Date August 15, 2000  
Date

(June 1990)

**UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT**

FORM APPROVED

Budget Bureau No. 1004-0135

Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.  
Use "APPLICATION FOR PERMIT -" for such proposals

**SUBMIT IN TRIPLICATE**

## 1. Type of Well

☒ Oil Well    ☐ Gas Well    ☐ Other

## 2. Name of Operator

**INLAND PRODUCTION COMPANY**

## 3. Address and Telephone No.

**Route 3 Box 3630 Myton, Utah 84052    435-646-3721**

## 4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

**517.5'FSL & 1898.91'FEL    SW/SE  
Sec.28, T8S, R17E**

## 5. Lease Designation and Serial No.

**U-76241**

## 6. If Indian, Allottee or Tribe Name

**NA**

## 7. If Unit or CA, Agreement Designation

**Greater Boundary**

## 8. Well Name and No.

**Tar Sands 15-28-8-17**

## 9. API Well No.

**43-013-32109**

## 10. Field and Pool, or Exploratory Area

**MONUMENT BUTTE**

## 11. County or Parish, State

**Duchesne County, UTAH**

## 12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

**TYPE OF SUBMISSION**

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

**TYPE OF ACTION**

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Surface Spud**

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

## 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Con't to drill 77/8" hole with air mist to a depth of 3815'. TOH with drill string and BHA. PU & MU bit #4, MM, & BHA. Drill a 77/8" hole with water based mud to a depth of 6119'. TOH and lay down drill string & BHA. Open hole log. PU & MU 41/2" guide shoe 1 jt, 41/2" float collar. 143 jt's 41/2" J-55 11.6# CSGN. Set @ 6109.84 KB. Cement with the following; \*Cement with \*360 sks Premlite II w/10% GEL. & 3% KCL mixed to 11.ppg >3.43 YLD. \*625sks 50/50 POZ w/3% GEL. & 3% KCL mixed to 14.4 ppg. >1.24YLD. Good returns. Bump plug to 1888 psi. Nipple down BOP's. Drop slips with 55,000#. **Release rig @ 4:30 pm on 8/18/00. WOC**

RECEIVED  
AUG 22 2000  
DIVISION OF  
OIL, GAS AND MINING

## 14. I hereby certify that the foregoing is true and correct

Signed

*Pat Wiser*

Title

**Drilling Foreman**

Date

**08/21/2000**

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

**CC: UTAH DOGM**

# INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

**4 1/2"**

CASING SET AT

**6,109.84**

TPBD 6065.49

LAST CASING **8 5/8'** SET AT **307.16/KB**

OPERATOR **INLAND PRODUCTION COMPANY**

DATUM **10' KB**

WELL **Tars Sands 15-28-8-17**

DATUM TO CUT OFF CASING

FIELD/PROSPECT **Monument Butte**

DATUM TO BRADENHEAD FLANGE

CONTRACTOR & RIG # **UNION RIG 14**

TD DRILLER **6119'** LOGGER **6125'**

HOLE SIZE **7 7/8"**

## LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		LANDING JT					14
<b>143</b>	<b>4.5"</b>	Maverick LT&C CSG w/10.5 flag	<b>11.6#</b>	<b>J-55</b>	<b>8rd</b>	<b>A</b>	6055.49
		Float Collar ( auto fill )			<b>8rd</b>	<b>A</b>	0.95
<b>1</b>	<b>4.5"</b>	Maverick LT&C CSG	<b>11.6#</b>	<b>J-55</b>	<b>8rd</b>	<b>A</b>	42.5
		SHOE - <b>GUIDE</b>			<b>8rd</b>	<b>A</b>	0.9

CASING INVENTORY BAL.	FEET	JTS	TOTAL LENGTH OF STRING	6113.84
TOTAL LENGTH OF STRING	6113.84	144	LESS CUT OFF PIECE	14
LESS NON CSG. ITEMS	15.85		PLUS DATUM TO T/CUT OFF CSG	10
PLUS FULL JTS. LEFT OUT	<b>170.87</b>	<b>4</b>	CASING SET DEPTH	<b>6109.84</b>

TOTAL	6268.86	148	} COMPARE	
TOTAL CSG. DEL. (W/O THRDS)	6268.86	148		
TIMING	1ST STAGE	2nd STAGE		
BEGIN RUN CSG.	8:00AM		GOOD CIRC THRU JOB	<b>YES</b>
CSG. IN HOLE	11:00AM		Bbls CMT CIRC TO SURFACE	26 bbls dye
BEGIN CIRC	11:15AM	12:05pm	RECIPROCATED PIPE FOR 10 mins THRU 8' FT STROKE	
BEGIN PUMP CMT	12:17pm	12:40pm	DID BACK PRES. VALVE HOLD ?	N/A
BEGIN DSPL. CMT		1:10pm	BUMPED PLUG TO	1888 PSI
PLUG DOWN		<b>1:23pm</b>		

CEMENT USED		CEMENT COMPANY- <b>B. J.</b>	
STAGE	# SX	CEMENT TYPE & ADDITIVES	
<b>1</b>	<b>360</b>	Prem Lite II w/ 10% GEL & 3% KCL mixed to 11.0 ppg > 3.43 YLD	
<b>2</b>	<b>625</b>	50/50 POZ w/ 2% GEL & 3% KCL mixed to 14.4 ppg > 1.24 YLD	
			DIVISION OF OIL, GAS AND MINING

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
1 on middle of first JT, 1 on collar of the second & third JT. Then every third collar for a total of 20.	

COMPANY REPRESENTATIVE

**Pat Wisener**

DATE **08/18/2000**



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.  
Use "APPLICATION FOR PERMIT - -" for such proposals

5. Lease Designation and Serial No.

**U-76241**

6. If Indian, Allottee or Tribe Name  
NA

7. If Unit or CA, Agreement Designation  
Greater Boundary Unit

8. Well Name and No.

**Tar Sands Federal 15-28-8-17**

9. API Well No.

43-013-32109

10. Field and Pool, or Exploratory Area

**Monument Butte**

11. County or Parish, State

Duchesne County Utah

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

**Inland Production Company**

3. Address and Telephone No.

**Route #3 Box 3630 Myton, Utah 84052 435-646-3721**

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

517.5' FSL & 1898.91' FEL SW/SE Sec. 28, T8S, R17E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Status report**

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well  
Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Status report for time period 9/11/00 through 9/17/00.  
Subject well had completion procedures initiated on 9/12/00. A total of three Green River intervals were perforated and hydraulically fractured. Bridge plugs and sand plugs were removed from wellbore. Zones are being swab tested for sand cleanup at present time.

RECEIVED

SEP 20 2000

DIVISION OF  
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct

Signed

Gary Dietz

Title

**Completion Foreman**

Date

**18-Sep-00**

(This space for Federal or State office use)

Approved by

Title


Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*See Instruction on Reverse Side



1-CHD  
2-Trace  
3-File

September 24, 2000

2 Wells

State of Utah  
Division of Oil, Gas & Mining  
Attn: Carol Daniels  
1594 West North Temple - Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

Dear Carol:

Please find enclosed form 3160-5: for Tar Sands Fed. 15-28-8-17. If you have any questions feel free to call me @ 435-823-7468 cell, or 435-646-3721 office any time.

Sincerely,

PAT WISENER  
Drilling Foreman

Enclosures

pw

**RECEIVED**

SEP 29 2000

DIVISION OF  
OIL, GAS AND MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.  
Use "APPLICATION FOR PERMIT -" for such proposals

**SUBMIT IN TRIPLICATE**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

**INLAND PRODUCTION COMPANY**

3. Address and Telephone No.

**Route 3 Box 3630 Myton, Utah 84052 435-646-3721**

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

**517.5' FSL & 1898.91 FEL SW/SE  
Sec.28, T8S, R17E**

5. Lease Designation and Serial No.

**U-76241**

6. If Indian, Allottee or Tribe Name

**NA**

7. If Unit or CA, Agreement Designation

**Greater Boundry Unit**

8. Well Name and No.

**Tar Sands fed. 15-28-8-17**

9. API Well No.

**43-013-32109**

10. Field and Pool, or Exploratory Area

**MONUMENT BUTTE**

11. County or Parish, State

**Duchesne County, UTAH**

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Weekly Status**

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

For the period of 9/18/00 thru 9/24/00

Continue to swab fluid to clean up from frac stimulation. Clean out to TPBD of 6043'. Trip production string in hole and set TAC w/13,000# and EOT @ 5987'. Trip in hole with rod pump and rod string. Pressure test tbg with rods. Place well on production @ 1:00pm on 9/19/00.  
73" stroke length @ 7 SPM.

**RECEIVED**

**SEP 29 2000**

**DIVISION OF  
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Signed

*Pat W. Isen*

Title

**Drilling Foreman**

Date

**09/24/2000**

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

**CC: UTAH DOGM**

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG\*

1a. TYPE OF WORK

OIL WELL ☒ GAS WELL ☐ DRY ☐ Other \_\_\_\_\_

1b. TYPE OF WELL

NEW WELL ☒ WORK OVER ☐ DEEPEN ☐ PLUG BACK ☐ DIFF RESVR. ☐ Other \_\_\_\_\_

2. NAME OF OPERATOR

INLAND RESOURCES INC.

3. ADDRESS AND TELEPHONE NO.

410 17th St. Suite 700 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)\*

At Surface

518' FSL & 1890' FEL (SW SE) SECTION 28 - 8S - 17E

At top prod. Interval reported below

At total depth

14. PERMIT NO.

43-013-32109

DATE ISSUED

08/19/99

12. COUNTY OR PARISH

DUCHESNE

13. STATE

UT

15. DATE SPUDDED

08/10/00

16. DATE T.D. REACHED

08/17/00

17. DATE COMPL. (Ready to prod.)

09/19/00

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\*

5132' GR

5142' KB

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD

6125'

21. PLUG BACK T.D., MD & TVD

6046'

22. IF MULTIPLE COMPL., HOW MANY\*

23. INTERVALS

DRILLED BY

ROTARY TOOLS

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)\*

Green River 4969' - 5944'

OCT 10 2000

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

CBL/CL/GR - 9-19-00

DIGL/SP/CDL - 8-25-00

DIVISION OF

OIL, GAS AND MINING

27. WAS WELL CORED

No

23. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8	24#	307'	12-1/4	141 sx Class G w/ 2% CaCl2	
5-1/2	15.5#	6110'	7-7/8	360 sx Premlite II & 625 sx 50/50 poz	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8	EOT @ 5807'	TA @ 5884'

31. PERFORATION RECORD (Interval, size and number)

INTERVAL	JSPF	NUMBER
(D2 sds) 4969' - 5000'	4	56
(B2 sds) 5244' - 5285'	2	78
(CP sds) 5765' - 5944'	1 and 2	(1) 24 (2) 46

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
4969' - 5000'	frac w/ 57,080# 20/40 sd in 356 bbls fluid
5244' - 5285'	frac w/ 78,000# 20/40 sd in 469 bbls fluid
5765' - 5944'	frac w/ 120,000# 20/40 sd in 721 bbls fluid

33.\* PRODUCTION

DATE FIRST PRODUCTION 09/19/00	PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 16' RHAC Pump					WELL STATUS (Producing or shut-in) PRODUCING	
DATE OF TEST 10 day average	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL--BBL.	GAS--MCF.	WATER--BBL.	GAS-OIL RATIO
				115	75	26	652
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL--BBL.	GAS--MCF.	WATER--BBL.	OIL GRAVITY-API (CORR.)	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & Used for Fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Logs In Item #26

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

TITLE

Senior Operations Engineer

DATE

10/4/00

\*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);	38. GEOLOGIC MARKERS			
	FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.
				ODEKIRK SPRING 15-36-8-17



February 28, 2001

Mr. Dan Jarvis  
State of Utah  
Division of Oil, Gas and Mining  
Post Office Box 145801  
Salt Lake City, Utah 84114-5801

Re: Permit Application for Water Injection Well  
Tar Sands Federal #15-28-8-17 *Greater Boundary Unit*  
Monument Butte Field, Boundary Unit, Lease #U-76241  
Section 28-Township 8S-Range 17E  
Duchesne County, Utah  
*43-013-32109*

Dear Mr. Jarvis:

Inland Production Company herein requests approval to convert the Tar Sands Federal #15-28-8-17 from a producing oil well to a water injection well in the Boundary Unit. Enclosed is a copy of the application filed with the BLM. Also enclosed is a sundry notice of intent.

I hope you find this application complete; however, if you have any questions or require additional information, please contact Joyce McGough or George Rooney at (303) 893-0102.

Sincerely,

Joyce McGough  
Regulatory Specialist

*UIC-271.2*

Enclosure

**RECEIVED**

MAR 08 2001

**DIVISION OF  
OIL, GAS AND MINING**



February 28, 2001

Mr. Emmett Schmitz  
U.S. Environmental Protection Agency  
Region VIII  
999 18<sup>th</sup> Street, Suite 500  
Denver, Colorado 80202-2405

RE: Permit Application for Water Injection Well  
Tar Sands Federal #15-28-8-17  
Monument Butte Field, Boundary Unit, Lease #U-76241  
Section 28-Township 8S-Range 17E  
Duchesne County, Utah


Dear Mr. Schmitz:

Inland Production Company herein requests a permit to convert the Tar Sands Federal #15-28-8-17 from a producing oil well to a water injection well.

Included with this application is a cement bond log for your convenience. As they are difficult to copy, however, I would very much appreciate its return.

I hope you find this application complete; however, if you have any questions or require additional information, please contact George Rooney at (303) 893-0102.

Sincerely,

  
Bill Pennington  
Chief Financial Officer

**INLAND PRODUCTION COMPANY**  
**APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL**  
**TAR SANDS FEDERAL #15-28-8-17**  
**MONUMENT BUTTE (GREEN RIVER) FIELD**  
**LEASE #U-76241**  
**BOUNDARY UNIT**  
**FEBRUARY 28, 2001**



## TABLE OF CONTENTS

LETTER OF INTENT	
COVER PAGE	
TABLE OF CONTENTS	
EPA FORM 4 – PERMIT APPLICATION	
WORK PROCEDURE FOR INJECTION CONVERSION	
WELLBORE DIAGRAM OF PROPOSED INJECTION WELL (TSF #15-28-8-17)	
ATTACHMENT A	AREA OF REVIEW METHODS
ATTACHMENT A-1	ONE-HALF MILE RADIUS MAP
ATTACHMENT A-2	LISTING OF SURFACE OWNERS
ATTACHMENT A-3	CERTIFICATION FOR SURFACE OWNER NOTIFICATION
ATTACHMENT A-4	WELL LOCATION PLAT
ATTACHMENT A-5	NAME(S) AND ADDRESS(ES) OF SURFACE OWNERS
ATTACHMENT B	MAP OF WELLS/AREA OF REVIEW
ATTACHMENT B-1	AREA OF REVIEW WITH PROPOSED & EXISTING WATER LINES
ATTACHMENT C	CORRECTIVE ACTION PLAN AND WELL DATA
ATTACHMENT C-1	WELLBORE DIAGRAM – TAR SANDS FEDERAL #15-28-8-17
ATTACHMENT C-2	WELLBORE DIAGRAM – TAR SANDS FEDERAL #7-28-8-17
ATTACHMENT C-3	WELLBORE DIAGRAM – TAR SANDS FEDERAL #9-28-8-17
ATTACHMENT C-4	WELLBORE DIAGRAM – TAR SANDS FEDERAL #10-28-8-17
ATTACHMENT C-5	WELLBORE DIAGRAM – TAR SANDS FEDERAL #11-28-8-17
ATTACHMENT C-6	WELLBORE DIAGRAM – TAR SANDS FEDERAL #14-28-8-17
ATTACHMENT C-7	WELLBORE DIAGRAM – TAR SANDS FEDERAL #16-28-8-17
ATTACHMENT C-8	WELLBORE DIAGRAM – TAR SANDS FEDERAL #1-33-8-17
ATTACHMENT C-9	WELLBORE DIAGRAM – TAR SANDS FEDERAL #2-33-8-17
ATTACHMENT C-10	WELLBORE DIAGRAM – TAR SANDS FEDERAL #7-33-8-17
ATTACHMENT C-11	WELLBORE DIAGRAM – HARBOURTOWN FEDERAL #21-33-8-17
ATTACHMENT E	NAME AND DEPTH OF USDWs
ATTACHMENT E-1	ANALYSIS OF FORMATION WATER FROM THE TAR SANDS FEDERAL #15-28-8-17
ATTACHMENT E-2	ANALYSIS OF THE COMPATIBILITY OF THE INJECTED AND FORMATION FLUIDS
ATTACHMENT G	GEOLOGICAL DATA ON INJECTION AND CONFINING ZONES
ATTACHMENT G-1	FORMATION TOPS
ATTACHMENT G-2	PROPOSED MAXIMUM INJECTION PRESSURE (FRACTURE CALC.)
ATTACHMENT G-3	FRACTURE REPORTS DATED 9/14/00
ATTACHMENT G-4	DRILLING & COMPLETION REPORTS DATED 8/11/00 THROUGH 8/18/00, AND 9/13/00 THROUGH 9/19/00
ATTACHMENT H	OPERATING DATA
ATTACHMENT M	CONSTRUCTION DETAILS
ATTACHMENT M-1	WELLBORE SCHEMATIC OF TAR SANDS FEDERAL #15-28-8-17
ATTACHMENT M-2	SITE PLAN OF TAR SANDS FEDERAL #15-28-8-17
ATTACHMENT Q	PROPOSED PLUGGING AND ABANDONMENT PROCEDURE
ATTACHMENT Q-1	EPA FORM 7520-14 – PLUGGING AND ABANDONMENT PLAN
ATTACHMENT Q-2	WELLBORE SCHEMATIC OF PROPOSED PLUGGING PLAN
ATTACHMENT Q-3	WORK PROCEDURE FOR PLUGGING AND ABANDONMENT
ATTACHMENT R	NECESSARY RESOURCES

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR Inland Production Company  
ADDRESS 410 17th Street, Suite 700  
Denver, Colorado 80202

Well Name and number:		<u>Tar Sands Federal #15-28-8-17</u>	
Field or Unit name:		<u>Monument Butte Field</u>	Lease No. <u>U-76241</u>
Well Location: QQ <u>SW/SE</u> section <u>28</u> township <u>8S</u> range <u>17E</u> county <u>Duchesne</u>			
Is this application for expansion of an existing project? ..... Yes [ X ] No [ ]			
Will the proposed well be used for:		Enhanced Recovery? ..... Yes [ X ] No [ ]	
		Disposal? ..... Yes [ ] No [ X ]	
		Storage? ..... Yes [ ] No [ X ]	
Is this application for a new well to be drilled? ..... Yes [ ] No [ X ]			
If this application is for an existing well,			
has a casing test been performed on the well? ..... Yes [ ] No [ X ]			
Date of test: <u>Will be done at time of conversion</u>			
API number: <u>43-013-32109</u>			
Proposed injection interval: from <u>4969'</u> to <u>5944'</u>			
Proposed maximum injection: rate <u>500 bpd</u> pressure <u>1563</u> psig			
Proposed injection zone contains [ X ] oil, [ ] gas, and/or [ ] fresh water within 1/2 mile of the well.			
<div style="border: 1px solid black; padding: 5px; display: inline-block;">IMPORTANT: Additional information as required by R615-5-2 should accompany this form.</div>			
List of Attachments: <u>Attachments A through R</u>			
I certify that this report is true and complete to the best of my knowledge.			
Name: <u>Bill Pennington</u>		Signature <u><i>Bill Pennington</i></u>	
Title <u>Chief Financial Officer</u>		Date <u>February 28, 2001</u>	
Phone No. <u>(303) 893-0102</u>			
(State use only)			
Application approved by _____		Title _____	
Approval Date _____			
Comments:			

**RECEIVED**

MAR 23 2001

DIVISION OF  
OIL, GAS AND MINING

## WORK PROCEDURE FOR INJECTION CONVERSION

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down, move out.

# Tar Sands Federal #15-28

Spud Date: 8/10/00  
Put on Production: 9/19/00  
GL: 5132' KB: 5142'

Initial Production: 115 BOPD,  
75 MCFPD, 26 BWPD

## SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 311' (7 jts)  
DEPTH LANDED: 307.16' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 141 sx Class "G" cement plus additives

## PRODUCTION CASING


CSG SIZE: 4-1/2"  
GRADE: J-55  
WEIGHT: 11.6#  
LENGTH: 144 jts (6113.84')  
DEPTH LANDED: 6109.84'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 360 sx PremLite II; followed by 625 sx 50/50 Pozmix.

*466*

## TUBING

SIZE/GRADE/WT.: 2-3/8" / J-55 / 6.5#  
NO. OF JOINTS: 183 jts  
TUBING ANCHOR: 5884'  
SEATING NIPPLE: 2-3/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5987.08' KB  
SN LANDED AT: 5952.92' KB

## Proposed Injection Wellbore Diagram



## FRAC JOB

9/14/00 5765'-5944' Frac CP sand as follows:  
120,000# 20/40 sand in 721 bbls Viking I-25 fluid. Perfs broke down @ 3550 psi. Treated @ avg press of 2000 psi w/avg rate of 34 BPM. ISIP-1600 psi, 5-min 1495 psi. Left pressure on well.

9/14/00 4969'-5000' Frac D-2 sand as follows:  
57,080# 20/40 sand in 356 bbls Viking I-25 fluid. Perfs broke down @ 3980 psi. Treated @ avg press of 2400 psi w/avg rate of 30.5 BPM. ISIP-3100 psi, 5-min 2710 psi. Flowback on 12/64" choke for 2-1/2 hours and died. Rec 77 BTF.

9/14/00 5244'-5285' Frac B-2 sand as follows:  
78,000# 20/40 sand in 469 bbls Viking I-25 fluid. Perfs broke down @ 2160 psi. Treated @ avg press of 1800 psi w/avg rate of 30 BPM. ISIP-2030 psi, 5-min 1900 psi. Left pressure on well.

## PERFORATION RECORD

Date	Depth Range	Tool	Holes
9/14/00	4969'-4978'	4 JSPF	36 holes
9/14/00	4995'-5000'	4 JSPF	20 holes
9/14/00	5244'-5265'	2 JSPF	42 holes
9/14/00	5267'-5285'	2 JSPF	36 holes
9/13/00	5765'-5771'	1 JSPF	6 holes
9/13/00	5791'-5802'	1 JSPF	11 holes
9/13/00	5824'-5828'	1 JSPF	4 holes
9/13/00	5831'-5834'	1 JSPF	3 holes
9/13/00	5921'-5944'	2 JSPF	46 holes



Inland Resources Inc.

Tar Sands Federal #15-28

518 FSL 1890 FEL

SWSE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32109; Lease #U-76241

SN @ 5953'  
EOT @ 5987'  
Sand PBTD @ 6043'  
PBTD @ 6046'  
TD @ 6125'

**ATTACHMENT A**  
**AREA OF REVIEW METHODS**

**Give the methods and, if appropriate, the calculations used to determine the size of the area of review (fixed radius or equation). The area of review shall be a fixed radius of 1/4 mile from the well bore unless the use of an equation is approved in advance by the Director.**

The area of review shall be a fixed radius of 1/2 mile from the Tar Sands Federal #15-28-8-17. Inland Production Company has chosen to use a fixed radius of 1/2 mile to satisfy the requirements of both the EPA and the State of Utah.


Attachment A-1 One-half Mile Radius Map

Attachment A-2 Listing of Surface Owners

Attachment A-3 Certification for Surface Owner Notification

Attachment A-4 Well Location Plat

Attachment A-5 Name(s) and Address(s) of Surface Owners



- 1-27
- 2-27
- 3-27
- 4-27
- 5-27
- 6-27
- 7-27
- 8-27
- 9-27
- 10-27
- 11-27
- 12-27
- 13-27
- 14-27
- 15-27
- 16-27
- 1-28
- 2-28
- 3-28
- 4-28
- 5-28
- 6-28
- 7-28
- 8-28
- 9-28
- 10-28
- 11-28
- 12-28
- 13-28
- 14-28
- 15-28
- 16-28
- 1-29
- 2-29
- 3-29
- 4-29
- 5-29
- 6-29
- 7-29
- 8-29
- 9-29
- 10-29
- 11-29
- 12-29
- 13-29
- 14-29
- 15-29
- 16-29
- 1-30
- 2-30
- 3-30
- 4-30
- 5-30
- 6-30
- 7-30
- 8-30
- 9-30
- 10-30
- 11-30
- 12-30
- 13-30
- 14-30
- 15-30
- 16-30
- 1-31
- 2-31
- 3-31
- 4-31
- 5-31
- 6-31
- 7-31
- 8-31
- 9-31
- 10-31
- 11-31
- 12-31
- 13-31
- 14-31
- 15-31
- 16-31
- 1-32
- 2-32
- 3-32
- 4-32
- 5-32
- 6-32
- 7-32
- 8-32
- 9-32
- 10-32
- 11-32
- 12-32
- 13-32
- 14-32
- 15-32
- 16-32
- 1-33
- 2-33
- 3-33
- 4-33
- 5-33
- 6-33
- 7-33
- 8-33
- 9-33
- 10-33
- 11-33
- 12-33
- 13-33
- 14-33
- 15-33
- 16-33
- 1-34
- 2-34
- 3-34
- 4-34
- 5-34
- 6-34
- 7-34
- 8-34
- 9-34
- 10-34
- 11-34
- 12-34
- 13-34
- 14-34
- 15-34
- 16-34

- 1-27
- 2-27
- 3-27
- 4-27
- 5-27
- 6-27
- 7-27
- 8-27
- 9-27
- 10-27
- 11-27
- 12-27
- 13-27
- 14-27
- 15-27
- 16-27
- 1-28
- 2-28
- 3-28
- 4-28
- 5-28
- 6-28
- 7-28
- 8-28
- 9-28
- 10-28
- 11-28
- 12-28
- 13-28
- 14-28
- 15-28
- 16-28
- 1-29
- 2-29
- 3-29
- 4-29
- 5-29
- 6-29
- 7-29
- 8-29
- 9-29
- 10-29
- 11-29
- 12-29
- 13-29
- 14-29
- 15-29
- 16-29
- 1-30
- 2-30
- 3-30
- 4-30
- 5-30
- 6-30
- 7-30
- 8-30
- 9-30
- 10-30
- 11-30
- 12-30
- 13-30
- 14-30
- 15-30
- 16-30
- 1-31
- 2-31
- 3-31
- 4-31
- 5-31
- 6-31
- 7-31
- 8-31
- 9-31
- 10-31
- 11-31
- 12-31
- 13-31
- 14-31
- 15-31
- 16-31
- 1-32
- 2-32
- 3-32
- 4-32
- 5-32
- 6-32
- 7-32
- 8-32
- 9-32
- 10-32
- 11-32
- 12-32
- 13-32
- 14-32
- 15-32
- 16-32
- 1-33
- 2-33
- 3-33
- 4-33
- 5-33
- 6-33
- 7-33
- 8-33
- 9-33
- 10-33
- 11-33
- 12-33
- 13-33
- 14-33
- 15-33
- 16-33
- 1-34
- 2-34
- 3-34
- 4-34
- 5-34
- 6-34
- 7-34
- 8-34
- 9-34
- 10-34
- 11-34
- 12-34
- 13-34
- 14-34
- 15-34
- 16-34

Attachment A-1

Tar Sands Fed. 15-28-8-17  
Sec 28-T8S-R17E  
1/2 Mile Radius



Attachment A-2  
Page 1

#	Land Description	Minerals Ownership & Expires	Minerals Leased By	Surface Rights
1	<u>Township 8 South, Range 17 East</u> Section 33: SW/4NE/4, W/2NW/4 SE/4NW, S/2 Section 34: W/2SW/4, SE/4SW/4, SW/4SE/4	UTU-77234 HBP	Inland Production Company	(Surface Rights) USA
2	<u>Township 8 South Range 17 East</u> Section 26: S/2SW/4, SW/4SE/4 Section 27: All Section 28: All Section 34: N/2, N/2SE/4	UTU-76241 HBP	Inland Production Company	(Surface Rights) USA
3	<u>Township 8 South Range 17 East</u> Section 30: NW/4NE/4 Section 33: SE/4NE/4, NE/4NW/4 Section 34: NE/4SW/4, SE/4SE/4	UTU-71368 HBP	Wildrose Resources, Inc.	(Surface Rights) USA

ATTACHMENT A-3

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

Re: Application for Approval of Class II Injection Well  
Tar Sands Federal #15-28-8-17

I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed: \_\_\_\_\_

*Bill Pennington*  
Inland Production Company  
Bill Pennington  
Chief Financial Officer


Sworn to and subscribed before me this 5 day of March, 2000.

Notary Public in and for the State of Colorado: \_\_\_\_\_

*Janel K. Spicke*

My commission expires: \_\_\_\_\_

*7/10/01*





Attachment A-4

T8S, R17E, S.L.B.&M.

S89°50'W - 79.96 (G.L.O.)

NOTE:  
THE WELL LOCATION BEARS N74°48'11"W  
1967.57' FROM THE SOUTHEAST  
CORNER OF SECTION 28.

28

WELL LOCATION:  
TAR SANDS FED. #15-28-8-17  
ELEV. UNGRADED GROUND = 5162.9'

1898.9'  
517.5'


S89°54'W (G.L.O.) - 2632.1' (MEASURED)  
Basis of Bearings G.L.O.

N00°02'W - 80.00 (G.L.O.)

N00°03'W - 80.00 (G.L.O.)

INLAND PRODUCTION CO.

WELL LOCATION, TAR SANDS FED #15-28-8-17,  
LOCATED AS SHOWN IN THE SW 1/4 SE 1/4 OF  
SECTION 28, T8S, R17E, S.L.B.&M. DUCHESNE  
COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF Aerial SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. GENE

STEWART

144102  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 144102  
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

38 WEST 100 NORTH - VERNAL, UTAH 84078  
(801) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: DS CS
DATE: 7-15-98	WEATHER: HOT
NOTES:	FILE #

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)

**ATTACHMENT A-5**

**Names and Addresses of Surface Owners**

1. USA

## **ATTACHMENT B**

### **MAPS OF WELLS/AREA AND AREA OF REVIEW**



**Submit a topographic map, extending one mile beyond the property boundaries, showing the injection well(s) or project area for which a permit is sought and the applicable area of review.**

There are no hazardous waste, treatment, storage or disposal facilities within a one-mile radius of the property boundaries.

Attachment B-1 Area of Review and Existing/Proposed Waterlines



Attachment B-1  
TSF 15-28



**Umont**  
INCORPORATED

41817th Street, Suite 700  
Denver, Colorado 80202  
Phone: (303) 875-4102

**Uinta Basin**  
UINTA BASIN, UTAH  
Deerhorn & Uinta Counties, Utah

February 23, 2004

D.C. Doyle



**ATTACHMENT C**  
**CORRECTIVE ACTION PLAN AND WELL DATA**

**Submit a tabulation of data reasonably available from public records or otherwise known to the applicant on all wells within the area of review, including those on the map required in Attachment B, which penetrate the proposed injection zone.**

Step rate tests will be performed periodically to determine the fracture pressure. The injection pressure will be kept under the fracture pressure.

Attachment C-1	Wellbore Diagram – TAR SANDS FEDERAL #15-28-8-17
Attachment C-2	Wellbore Diagram – TAR SANDS FEDERAL #7-28-8-17
Attachment C-3	Wellbore Diagram – TAR SANDS FEDERAL #9-28-8-17
Attachment C-4	Wellbore Diagram – TAR SANDS FEDERAL #10-28-8-17
Attachment C-5	Wellbore Diagram – TAR SANDS FEDERAL #11-28-8-17
Attachment C-6	Wellbore Diagram – TAR SANDS FEDERAL #14-28-8-17
Attachment C-7	Wellbore Diagram – TAR SANDS FEDERAL #16-28-8-17
Attachment C-8	Wellbore Diagram – TAR SANDS FEDERAL #1-33-8-17
Attachment C-9	Wellbore Diagram – TAR SANDS FEDERAL #2-33-8-17
Attachment C-10	Wellbore Diagram – TAR SANDS FEDERAL #7-33-8-17
Attachment C-11	Wellbore Diagram – HARBOURTOWN FEDERAL #21-33-8-17

## Tar Sands Federal #15-28

Spud Date: 8/10/00  
Put on Production: 9/19/00  
GL: 5132' KB: 5142'

Initial Production: 115 BOPD,  
75 MCFPD, 26 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 311' (7 jts)  
DEPTH LANDED: 307.16' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 141 sx Class "G" cement plus additives

PRODUCTION CASING

CSG SIZE: 4-1/2"  
GRADE: J-55  
WEIGHT: 11.6#  
LENGTH: 144 jts (6113.84')  
DEPTH LANDED: 6109.84'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 360 sx PremLite II; followed by 625 sx 50/50 Pozmix.

TUBING

SIZE/GRADE/WT.: 2-3/8" / J-55 / 6.5#  
NO. OF JOINTS: 183 jts  
TUBING ANCHOR: 5884'  
SEATING NIPPLE: 2-3/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5987.08' KB  
SN LANDED AT: 5952.92' KB

SUCKER RODS

POLISHED ROD: 1-1/4" x 22' polished  
SUCKER RODS: 4 - 1-1/2" weight rods; 10 - 3/4" scraped; 134 - 3/4" plain;  
89 - 3/4" scraped; and 1 each of 3/4" x 8', 3/4" x 6' and 3/4" x 2' pony rods.  
TOTAL ROD STRING LENGTH: ?  
PUMP SIZE: 2-1/2 x 1-1/2 x 16" RHAC pump  
STROKE LENGTH: 73"  
PUMP SPEED, SPM: 7  
LOGS: GR, SP, Spectral Density-Dual Spaced Neuron, CBL-GR

FRAC JOB


9/14/00 5765'-5944' Frac CP sand as follows:  
120,000# 20/40 sand in 721 bbls Viking I-25 fluid. Perfs broke down @ 3550 psi. Treated @ avg press of 2000 psi w/avg rate of 34 BPM. ISIP-1600 psi, 5-min 1495 psi. Left pressure on well.

9/14/00 4969'-5000' Frac D-2 sand as follows:  
57,080# 20/40 sand in 356 bbls Viking I-25 fluid. Perfs broke down @ 3980 psi. Treated @ avg press of 2400 psi w/avg rate of 30.5 BPM. ISIP-3100 psi, 5-min 2710 psi. Flowback on 12/64" choke for 2-1/2 hours and died. Rec 77 BTF.

9/14/00 5244'-5285' Frac B-2 sand as follows:  
78,000# 20/40 sand in 469 bbls Viking I-25 fluid. Perfs broke down @ 2160 psi. Treated @ avg press of 1800 psi w/avg rate of 30 BPM. ISIP-2030 psi, 5-min 1900 psi. Left pressure on well.

PERFORATION RECORD

9/14/00	4969'-4978'	4 JSPP	36 holes
9/14/00	4995'-5000'	4 JSPP	20 holes
9/14/00	5244'-5265'	2 JSPP	42 holes
9/14/00	5267'-5285'	2 JSPP	36 holes
9/13/00	5765'-5771'	1 JSPP	6 holes
9/13/00	5791'-5802'	1 JSPP	11 holes
9/13/00	5824'-5828'	1 JSPP	4 holes
9/13/00	5831'-5834'	1 JSPP	3 holes
9/13/00	5921'-5944'	2 JSPP	46 holes



Inland Resources Inc.

Tar Sands Federal #15-28

518 FSL 1890 FEL

SWSE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32109; Lease #U-76241

SN @ 5953'  
EOT @ 5987'  
Sand PBTD @ 6043'  
PBTD @ 6046'  
TD @ 6125'

## Tar Sands Federal #7-28

Spud Date: 6/22/98  
Put on Production: 8/8/98  
GL: 5196' KB: 5206'

## Injection Wellbore Diagram

Initial Production: 112 BOPD,  
196 MCFPD, 12 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (292.33')  
DEPTH LANDED: 292.83' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 120 sxs Class G cmt, est 4.5 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 145 jts. (6165')  
DEPTH LANDED: 6176' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 360 sxs Premium Lite mixed & 400 sxs Class G  
CEMENT TOP AT: Surface per CBL

3224

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
NO. OF JOINTS: 138 jts  
PACKER: 4463'  
SEATING NIPPLE: 2-7/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 4467'  
SN LANDED AT: 4460'

SUCKER RODS

POLISHED ROD:  
SUCKER RODS:  
PUMP SIZE:  
STROKE LENGTH:  
PUMP SPEED, SPM:  
LOGS: Dual Laterlog, GR, SP, Spectral Density-Dual Spaced Neutron, CBL-GR

12/4/00

FRAC JOB

7/29/98 5904'-6003' Frac CP sand as follows:  
111,000# of 20/40 sand in 564 bbls  
Viking I-25 fluid. Prefs broke down @  
2420 psi. Treated @ avg press of 1335  
psi w/avg rate of 29.9 bpm. ISIP: 1850  
psi, 5-min 1750 psi. Flowback on 12/64  
choke for 6 hours and died.

7/31/98 5232'-5246' Frac C sand as follows:  
104,500# of 20/40 sand in 531 bbls  
Viking I-25 fluid. Prefs broke down @  
2920 psi. Treated @ avg press of 1620  
psi w/avg rate of 27.8 bpm. ISIP: 2420  
psi, 5-min 2200 psi. Flowback on 12/64  
choke for 3 hours and died.

8/3/98 5052'-5061' Frac D sand as follows:  
93,700# of 20/40 sand in 500 bbls  
Viking I-25 fluid. Prefs broke down @  
2230 psi. Treated @ avg press of 1580  
psi w/avg rate of 26.3 bpm. ISIP: 2350  
psi, 5-min 1860 psi. Flowback on 12/64  
choke for 3 hours and died.

8/5/98 4546'-4596' Frac GB sand as follows:  
104,500# of 20/40 sand in 513 bbls  
Viking I-25 fluid. Prefs broke down @  
3200 psi. Treated @ avg press of 1700  
psi w/avg rate of 28.8 bpm. ISIP: 2000  
psi, 5-min 1640 psi. Flowback on 12/64  
choke for 3-1/2 hours and died.

Packer @ 4463'

PERFORATION RECORD

7/28/98	5904'-5906'	4 JSPF	8 holes
7/28/98	5924'-5932'	4 JSPF	32 holes
7/28/98	5999'-6003'	4 JSPF	16 holes
7/30/98	5232'-5246'	4 JSPF	56 holes
8/1/98	5052'-5061'	4 JSPF	36 holes
8/4/98	4546'-4555'	4 JSPF	36 holes
8/4/98	4592'-4596'	4 JSPF	16 holes

SN @ 4460'  
EOT @ 4467'  
Sand PBTD @ 6115'  
PBTD @ 6127'  
TD @ 6200'



Inland Resources Inc.

Tar Sands Federal #7-28

2237 FNL 2031 FEL

SWNE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32069; Lease #UTU-76241

## Tar Sands Federal #9-28

Spud Date: 6/25/98  
Put on Production: 8/24/98  
GL: 5191' KB: 5201'

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (295')  
DEPTH LANDED: 295'  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 120 sxs Class "G" cmt, & 15 sxs Class "G".

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 143 jts. (6129')  
SET AT: 6140'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 380 sxs Premium modified mixed & 380 sxs class G  
CEMENT TOP AT: 390' per cement bond log (Schlumberger)

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
NO. OF JOINTS: 136 jts  
PACKER: 4529'  
SEATING NIPPLE: 2-7/8"  
TOTAL STRING LENGTH: EOT @ 4533'  
SN LANDED AT: 4525'

SUCKER RODS

POLISHED ROD:  
SUCKER RODS:  
PUMP SIZE:  
STROKE LENGTH:  
PUMP SPEED, SPM:  
LOGS: DIGL/SP/GR/CAL  
SDL/DSN/GR

Injection Wellbore  
Diagram Updated  
4/12/00 GBRIV

Initial Production: 44 BOPD;  
56 MCFD; 5 BWPD

FRAC JOB

8/12/98 5896'-5998' Frac CP-1 & CP-2 sand as follows:  
100,500# 20/40 sand in 533 bbls Viking I-25 fluid. Perfs broke back @ 2520 psi. Treated @ avg press of 1070 psi w/avg rate of 32 BPM. ISIP: 1460 psi, 5-min 1380 psi. Flowback on 12/64 choke for 3-1/2 hours and died.


8/14/98 5579'-5593' Frac A-3 sand as follows:  
96,850# 20/40 sand in 534 bbls Viking I-25 fluid. Perfs broke back @ 3470 psi. Treated @ avg press of 1780 psi w/avg rate of 28.6 BPM. ISIP: 2200 psi, 5-min 2050 psi. Flowback on 12/64 choke for 4 hours and died.

8/17/98 5425'-5446' Frac B-2 sand as follows:  
90,000# 20/40 sand in 490 bbls Viking I-25 fluid. Perfs broke back @ 3820 psi. Treated @ avg press of 1335 psi w/avg rate of 25.1 BPM. ISIP: 1840 psi, 5-min SI - 1600 psi. Flowback on 12/64 choke for 4 hours and died.

8/19/98 4609'-4615' Frac GB-6 sand as follows:  
81,900# 20/40 sand in 431 bbls Viking I-25 fluid. Perfs broke back @ 3100 psi. Treated @ avg press of 1970 psi w/avg rate of 24.7 BPM. ISIP: 2420 psi, 5-min SI 2100 psi. Flowback on 12/64 choke for 3-1/2 hours and died.

PERFORATION RECORD

8/11/98	5896'-5914'	2 JSPF	36 holes
8/11/98	5952'-5954'	2 JSPF	4 holes
8/11/98	5975'-5972'	2 JSPF	14 holes
8/11/98	5986'-5998'	2 JSPF	14 holes
8/13/98	5579'-5593'	4 JSPF	56 holes
8/15/98	5425'-5427'	4 JSPF	8 holes
8/15/98	5436'-5446'	4 JSPF	40 holes
8/18/98	4609'-4615'	4 JSPF	24 holes



Inland Resources Inc.

Tar Sands Federal #9-28

2083 FSL 679 FEL

NESE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32067; Lease #U-76241



## Tar Sands Federal #10-28

Spud Date: 6/24/98  
Put on Production: 8/19/98  
GL: 5207' KB: 5217'

Initial Production: 238 BOPD,  
377 MCFPD, 15 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 288' (7 jts)  
DEPTH LANDED: 288' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 120 sxs Premium cmt Est 6 bbls cmt to surface.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 144 jts (6128')  
DEPTH LANDED: 6139'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 375 sxs Premium mixed & 400 sxs Class 'G'  
CEMENT TOP AT: 241' per KB

3569

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
NO. OF JOINTS: 189 jts  
TUBING ANCHOR: 5873'  
SEATING NIPPLE: 2-7/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 6001'  
SN LANDED AT: 5938'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' polished  
SUCKER RODS: 4 - 1-1/2" weight rods, 4 - 3/4" scraped, 133 - 3/4" plain, 95 - 3/4" scraped, 1 - 8"x3/4" pony rods.  
TOTAL ROD STRING LENGTH: ?  
PUMP SIZE: 2-1/2 x 1-1/2 x 16" RHAC pump  
STROKE LENGTH: 84"  
PUMP SPEED, SPM: 8  
LOGS: GR, SP, Spectral Density-Dual Spaced Neuron, CBL-GR

FRAC JOB

7/24/98 5906'-5927' Frac CP-1 sand as follows:  
109,021# 20/40 sand in 565 bbls Viking I-25 fluid. Perfs broke down @ 2428 psi. Treated @ avg press of 1300 psi w/avg rate of 28.2 BPM. ISIP-1750 psi, 5-min 1537 psi. Flowback on 12/64" choke for 3-1/2 hours and died.

7/27/98 5565'-5582' Frac A-3 sand as follows:  
121,500# 20/40 sand in 586 bbls Viking I-25 fluid. Perfs broke down @ 3100 psi. Treated @ avg press of 1880 psi w/avg rate of 30.3 BPM. ISIP-1980 psi, 5-min 1860 psi. Flowback on 12/64" choke for 3 hours and died.

7/29/98 5417'-5426' Frac B-2 sand as follows:  
111,800# 20/40 sand in 565 bbls Viking I-25 fluid. Perfs broke down @ 4000 psi, w/ 2nd break @ 1760 psi w/ rate. Treated @ avg press of 1425 psi w/avg rate of 28.5 BPM. ISIP-2150 psi, 5-min 1700 psi. Flowback on 12/64" choke for 4 hours and died.


7/31/98 5207'-5220' Frac C-Sd sand as follows:  
105,400# 20/40 sand in 430 bbls Viking I-25 fluid. Perfs broke down @ 3300 psi. Treated @ avg press of 1650 psi w/avg rate of 24 bpm. With 7# sand @ perfs, slurry pumps began pumping extremely rough. Maximum rate able to pump was reduced to 19 bpm. Pressure began rising quickly. 10 ppg sand was reached @ blender before cutting sand. Flushed 20 bbls before screenout occurred w/9.9# sand on perfs. Est. 76,100# sand on formation, 29,300# sand left in casing. Flow well back. Rec 5 bbls.

8/3/98 5038'-5106' Frac D-1 & D-2 sand as follows:  
94,700# 20/40 sand in 495 bbls Viking I-25 fluid. Perfs broke down @ 2100 psi. Treated @ avg press of 2050 psi w/avg rate of 30.5 BPM. ISIP-2920 psi, 5-min 2540 psi. Flowback on 12/64" choke for 2-1/2 hours and died.

8/5/98 4502'-4598' Frac GB-4 & GB-6 sand as follows:  
118,000# 20/40 sand in 569 bbls Viking I-25 fluid. Perfs broke down @ 3600 psi. Treated @ avg press of 1750 psi w/avg rate of 30.6 BPM. ISIP-2160 psi, 5-min 1700 psi. Flowback on 12/64" choke for 3-1/2 hours and died.

PERFORATION RECORD

7/23/98	5906'-5917'	4 JSPF	44 holes
7/23/98	5922'-5927'	4 JSPF	20 holes
7/25/98	5565'-5582'	4 JSPF	68 holes
7/29/98	5417'-5426'	4 JSPF	36 holes
7/30/98	5207'-5220'	4 JSPF	52 holes
8/1/98	5038'-5040'	4 JSPF	8 holes
8/1/98	5048'-5052'	4 JSPF	16 holes
8/1/98	5103'-5106'	4 JSPF	12 holes
8/4/98	4502'-4511'	4 JSPF	36 holes
8/4/98	4589'-4598'	4 JSPF	36 holes



Inland Resources Inc.

Tar Sands Federal #10-28

2025 FSL 1964 FEL

NWSE Section 286-T8S-R17E

Duchesne Co, Utah

API #43-013-32066; Lease #U-76241

## Tar Sands Federal #11-28

Spud Date: 8/27/00  
Put on Production: 10/04/00  
GL: 5124' KB: 5134'

Initial Production: 54 BOPD,  
74 MCFPD, 19 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 306.91' (8 jts)  
DEPTH LANDED: 302.91'  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 141 sx Class "G" cmt with additives

PRODUCTION CASING

CSG SIZE: 4-1/2"  
GRADE: J-55  
WEIGHT: 11.6#  
LENGTH: 135 jts (6063.85')  
DEPTH LANDED: 6059.85'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 350 sx PremLite II; followed by 580 sx 50/50 Pozmix

456

TUBING

SIZE/GRADE/WT.: 2-3/8" / J-55 / 6.5#  
NO. OF JOINTS: 183 jts  
TUBING ANCHOR: 5765.31'  
SEATING NIPPLE: 2-3/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5964.68' w/10' KB  
SN LANDED AT: 5898.26' KB

SUCKER RODS

POLISHED ROD: 1-1/4" x 22' polished  
SUCKER RODS: 4 - 1-1/2" weight bars, 10 - 3/4" guided rods, 131 - 3/4" plain, 89 - 3/4" scraped, 2 - 8'x3/4", 1 - 6' x 3/4" and 1 - 3/4" x 2' pony rods.  
TOTAL ROD STRING LENGTH: ?  
PUMP SIZE: 2" x 1-1/2 x 16' RWAC pump  
STROKE LENGTH:  
PUMP SPEED, SPM:  
LOGS: GR, SP, Spectral Density-Dual Spaced Neuron, CBL-GR

FRAC JOB

9/28/00 5790'-5896' **Frac CP-1 sand as follows:**  
99,000# 20/40 sand in 584 bbls Viking I-25 fluid. Perfs broke down @ 3830 psi. Treated @ avg press of 1900 psi w/avg rate of 29 BPM. ISIP-1860 psi. Flowback on 12/64" choke for 4 hours.

9/28/00 5479'-5498' **Frac A-1 sand as follows:**  
66,000# 20/40 sand in 391 bbls Viking I-25 fluid. Perfs broke down @ 3680 psi. Treated @ avg press of 2200 psi w/avg rate of 29 BPM. ISIP-2250 psi. Flowback on 12/64" choke for 2 hours and died. Rec 78 BTF.

9/29/00 5294'-5364' **Frac B-2 sand as follows:**  
138,000# 20/40 sand in 742 bbls Viking I-25 fluid. Perfs broke down @ 2990 psi. Treated @ avg press of 2000 psi w/avg rate of 29.5 BPM. ISIP-2000 psi. Flowback on 12/64" choke @ 1 BPM. Flowed total of 135 bbls.

9/29/00 5114'-5118' **Frac C sand as follows:**  
30,300# 20/40 sand in 217 bbls Viking I-25 fluid. Perfs broke down @ 3088 psi. Treated @ avg press of 2800 psi w/avg rate of 29 BPM. ISIP 2500 psi. Flowed back on 12/64" choke for 1-1/2 hrs & died. Rec 59 BTF.

PERFORATION RECORD

Date	Interval	Tool	Holes
9/29/00	5114'-18'	4 JSPF	16 holes
9/29/00	5294'-98'	4 JSPF	16 holes
9/29/00	5313'-22'	4 JSPF	36 holes
9/29/00	5324'-50'	4 JSPF	104 holes
9/29/00	5357'-64'	4 JSPF	28 holes
9/28/00	5479'-93'	4 JSPF	56 holes
9/28/00	5495'-98'	4 JSPF	12 holes
9/27/00	5790'-96'	4 JSPF	24 holes
9/27/00	5798'-802'	4 JSPF	16 holes
9/27/00	5827'-42'	4 JSPF	60 holes
9/27/00	5892'-96'	4 JSPF	16 holes

5114'-18'  
5294'-98'  
  
5313'-22'  
5324'-50'  
5357'-64'  
  
5479'-93'  
5495'-98'  
Anchor @ 5765'  
  
5790'-802'  
  
5827'-42'  
  
5892'-96'  
  
SN @ 5898'  
EOT @ 5965'  
Sand PBD @ 6014'  
PBD @ 6016'  
TD @ 6081'



Inland Resources Inc.

Tar Sands Federal #11-28

1695 FSL 1882 FWL

NESW Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32134; Lease #U-76241

## Tar Sands Federal #14-28

Spud Date: 6/30/98  
Put on Production: 8/19/98  
GL: 5109' KB: 5121'

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (313')  
DEPTH LANDED: 314' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 120 sxs Class G

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 142 jts. (5972')  
DEPTH LANDED: 5981' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 340 sxs Premium Lite mixed & 350 sxs Class G  
CEMENT TOP AT: Surface per CBL

3094


TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#  
NO. OF JOINTS: 192 jts  
TUBING ANCHOR: 5703'  
SEATING NIPPLE: 2-7/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5860'  
SN LANDED AT: 5798'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM  
SUCKER RODS: 4 - 1-1/2" weight rods, 4 - 3/4" scraped rods, 128 - 3/4" plain rods, 95 - 3/4" scraped rods, 1 - 8', 1 - 6', 1 - 4', 1-2' x 3/4" pony rods.  
PUMP SIZE: 2-1/2" x 1-1/2" x 15-1/2 RHAC  
STROKE LENGTH: 74"  
PUMP SPEED, SPM: 5 1/2 SPM  
LOGS: DIGL/SP/GR/CAL/CN/CD/CBL-GR

## Wellbore Diagram

FRAC JOB

8/11/98 5730'-5797' Frac CP sand as follows:  
112,100# 20/40 sand in 559 bbl Viking I-25 fluid. Perfs broke down @ 3720 psi. Treated @ avg press of 1350 w/avg rate of 30.2 bpm. ISIP: 1820 psi, 5 min: 1700 psi. Flowback on 12/64 choke for 4-1/2 hrs & died

8/13/98 5147'-5261' Frac B sand as follows:  
118,500# of 20/40 sand in 584 bbls Viking I-25 fluid. Perfs broke down @ 3137 psi. Treated @ avg press of 1980 psi w/avg rate of 32 bpm. ISIP: 2300 psi, 5-min 2140 psi. Flowback on 12/64 choke for 3 hours and died.

8/15/98 4939'-5071' Frac D/C sand as follows:  
128,800# of 20/40 sand in 607 bbls Viking I-25 fluid. Perfs broke down @ 3200 psi. Treated @ avg press of 2150 psi w/avg rate of 36.1 bpm. ISIP: 2800 psi, 5-min 2700 psi. Flowback on 12/64 choke for 3 hours and died.

PERFORATION RECORD

Date	Depth Range	Tool	Holes
8/9/98	5730'-5740'	2 JSPF	20 holes
8/9/98	5753'-5777'	2 JSPF	48 holes
8/9/98	5792'-5797'	2 JSPF	10 holes
8/12/98	5147'-5152'	4 JSPF	20 holes
8/12/98	5208'-5213'	4 JSPF	20 holes
8/12/98	5256'-5261'	4 JSPF	20 holes
8/14/98	4939'-4944'	4 JSPF	20 holes
8/14/98	5042'-5045'	4 JSPF	12 holes
8/14/98	5050'-5057'	4 JSPF	28 holes
8/14/98	5061'-5064'	4 JSPF	12 holes
8/14/98	5067'-5071'	4 JSPF	16 holes



Inland Resources Inc.

Tar Sands Federal #14-28

660 FSL 1982 FWL

SESW Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32065; Lease #U-76241

SN @ 5798'  
EOT @ 5860'  
Sand PBTD @ 5921'  
PBTD @ 5923  
TD @ 6000'

## Tar Sands Federal #16-28

Spud Date: 8/19/00  
Put on Production: 8/29/00  
GL: 5113' KB: 5123'

Initial Production: 119 BOPD,  
29 MCFPD, 7 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 310.32' (7 jts)  
DEPTH LANDED: 306.32' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 141 sx Class "G" cement plus additives

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 147 jts (6153.51')  
DEPTH LANDED: 6161.11'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 300 sx PremLite II; followed by 550 sx 50/50 Pozmix.

543

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
NO. OF JOINTS: 190 jts  
TUBING ANCHOR: 5790'  
SEATING NIPPLE: 2-7/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5919.03' KB  
SN LANDED AT: 5855.70' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' polished  
SUCKER RODS: 4 - 1-1/2" weight rods; 10 - 3/4" scraped; 130 - 3/4" plain;  
89 - 3/4" scraped; and 1 each of 3/4" x 8', 3/4" x 6' and 3/4" x 2' pony rods.  
TOTAL ROD STRING LENGTH: ?  
PUMP SIZE: 2-1/2 x 1-1/2 x 16' RHAC pump  
STROKE LENGTH: 100"  
PUMP SPEED, SPM: 6  
LOGS: GR, SP, Spectral Density-Dual Spaced Neuron, CBL-GR

FRAC JOB

9/21/00 5797'-5839' Frac CP sand as follows:  
75,440# 20/40 sand in 506 bbls Viking I-25 fluid. Perfs broke down @ 3368 psi. Treated @ avg press of 1300 psi w/avg rate of 30 BPM. ISIP-2066 psi, 5-min 1622 psi.

9/21/00 5472'-5495' Frac A-3 sand as follows:  
46,440# 20/40 sand in 367 bbls Viking I-25 fluid. Perfs broke down @ 2560 psi. Treated @ avg press of 2159 psi w/avg rate of 29.9 BPM. ISIP-2066 psi, 5-min 1934 psi.

9/21/00 5254'-5301' Frac B sand as follows:  
99,440# 20/40 sand in 595 bbls Viking I-25 fluid. Perfs broke down @ 2170 psi. Treated @ avg press of 1740 psi w/avg rate of 31 BPM. ISIP-2060 psi, 5-min 1811 psi. Flow well back on 12/64" choke for 4.5 hrs & died. Recovered 191 bbls frac fluid; est. 1381 BWTR.

PERFORATION RECORD

9/21/00	5254'-5273'	4 JSPF	76 holes
9/21/00	5277'-5287'	4 JSPF	40 holes
9/21/00	5297'-5301'	4 JSPF	16 holes
9/21/00	5472'-5476'	4 JSPF	16 holes
9/21/00	5488'-5495'	4 JSPF	28 holes
9/20/00	5797'-5817'	4 JSPF	80 holes
9/20/00	5827'-5834'	4 JSPF	28 holes
9/20/00	5836'-5839'	4 JSPF	12 holes

5254'-5273'

5277'-5287'

5297'-5301'

5472'-5476'

5488'-5495'

Anchor @ 5790'

5797'-5817'

5827'-5834'

5836'-5839'

SN @ 5856'  
EOT @ 5919'  
Sand PBTD @ 6118'  
PBTD @ 6120'  
TD @ 6167'



Inland Resources Inc.

Tar Sands Federal #16-28

614 FSL 515 FEL

SESE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32111; Lease #U-76241

## Tar Sands Federal #1-33

Spud Date: 10/19/97  
Put on Production: 11/22/97  
GL: 5095' KB: 5108'

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (260')  
DEPTH LANDED: 259'  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 140 sxs Premium cmt, est 5 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 139 jts. (5954')  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 255 sxs Hibond mixed & 265 sxs thixotropic  
CEMENT TOP AT: ? 4900  
LANDED AT: 5964'


TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#  
NO. OF JOINTS: 182 jts  
TUBING ANCHOR: 5675'  
SEATING NIPPLE: 2-7/8"  
TOTAL STRING LENGTH: ?  
SN LANDED AT: 5739'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM  
SUCKER RODS: 4-11/2" wt rods; 4-3/4" scraped; 126-3/4" plain;  
95-3/4" scraped; 1-4"x3/4" pony rod  
TOTAL ROD STRING LENGTH: ?  
PUMP NUMBER: ?  
PUMP SIZE: 2-1/2" x 1-1/2" x 15' RHAC  
STROKE LENGTH: 74"  
PUMP SPEED, SPM: 8 SPM  
LOGS: DIG/SP/GR/CAL (5970'-269')  
SDL/DSN/GR (5961'-3000')

Wellbore Diagram



Initial Production: 111 BOPD;  
114 MCFD; 4 BWPD

FRAC JOB

11/15/97 5708'-5773' Frac CP sand as follows:  
111,300# 20/40 sand in 567 bbls of Delta frac. Breakdown @ 2043 psi, treated @ avg rate 30.1 bpm w/avg press of 1480 psi. ISIP-1757 psi, 5-min 1658 psi. Start flowback on 12/64" ck for 5-1/2 hrs and died.

11/18/97 5382'-5436' Frac A sand as follows:  
127,300# of 20/40 sand in 596 bbls of Delta frac. Breakdown @ 2354 psi. Treated @ avg rate 29.9 bpm w/avg press of 1580 psi. ISIP-2038 psi, 5-min 1902 psi. Start flowback on 12/64" ck for 4 hrs & died.

11/20/97 5172'-5193' Frac B sand as follows:  
113,500# of 20/40 sand in 564 bbls of Delta frac. Breakdown @ 1885 psi. Treated @ avg rate 28.5 bpm w/avg press of 2000 psi. ISIP-2668 psi, 5-min 2411 psi. Start flowback on 12/64" ck for 4-1/2 hrs & died.

PERFORATION RECORD

Date	Interval	Tool	Holes
11/14/97	5708' - 5710'	4 JSPF	8 holes
11/14/97	5731' - 5736'	4 JSPF	20 holes
11/14/97	5738' - 5748'	4 JSPF	40 holes
11/14/97	5766' - 5773'	4 JSPF	28 holes
11/14/97	5755' - 5765'	misfire	
11/16/97	5382' - 5387'	4 JSPF	20 holes
11/16/97	5390' - 5398'	4 JSPF	32 holes
11/16/97	5403' - 5413'	4 JSPF	40 holes
11/16/97	5422' - 5436'	4 JSPF	56 holes
11/19/97	5172' - 5177'	4 JSPF	20 holes
11/19/97	5181' - 5186'	4 JSPF	20 holes
11/19/97	5190' - 5193'	4 JSPF	12 holes



Inland Resources Inc.

Tar Sands Federal #1-33

627 FNL 665 FEL

NENE Section 33-T8S-R17E

Duchesne Co, Utah

API #43-013-31863; Lease #U-76241

## Tar Sands Federal #2-33

Spud Date: 8/23/97  
Put on Production: 9/30/97  
GL: KB:

Initial Production: 138 BOPD;  
132 MCFD; 15 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (299')  
DEPTH LANDED: 301' KB  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 140 sxs Premium cmt, est 4 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 140 jts. (5935')  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 285 sxs Hibond mixed & 285 sxs thixotropic  
CEMENT TOP AT:  
SET AT: 5946' *3820*

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5#  
NO. OF JOINTS: 183 jts  
TUBING ANCHOR: 5695'  
SEATING NIPPLE: 2-7/8"  
TOTAL STRING LENGTH: ?  
SN LANDED AT: 5760'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM  
SUCKER RODS: 4-11/2" wt rods; 4-3/4" scraped; 126-3/4" plain;  
95-3/4" scraped  
TOTAL ROD STRING LENGTH: ?  
PUMP NUMBER: ?  
PUMP SIZE: 2-1/2" x 1-1/2" x 15' RHAC  
STROKE LENGTH: 80"  
PUMP SPEED, SPM: 8.5 SPM  
LOGS: DIGL/SP/GR/CAL (5948'-309')  
SDL/DSN/GR (5916'-3000')

FRAC JOB

9/19/97 5724'-5839' Frac CP sand as follows:  
120,000# 20/40 sand in 603 bbls of Boragel. Breakdown @ 2046 psi, treated @ avg rate 28.3 bpm w/avg press of 1300 psi. ISIP-1693 psi, 5-min 1508 psi. Start flowback on 12/64" ck for 3 - 1/2 hrs and died.

9/21/97 5454'-5492' Frac LDC sand as follows:  
77,500# of 20/40 sand in 445 bbls of Boragel. Breakdown @ 3344 psi. Treated @ avg rate 24.4 bpm w/avg press of 2000 psi. ISIP-2404 psi, 5-min 2341 psi. Start flowback on 12/64" ck for 3-1/2 hrs & died.

9/24/97 5232'-5363' Frac A/B sands as follows:  
141,000# of 20/40 sand in 639 bbls of Boragel. Breakdown @ 2900 psi. Treated @ avg rate 30.15 bpm w/avg press of 2250 psi. ISIP-2535 psi, 5-min 2373 psi. Start flowback on 12/64" ck for 5 - 1/2 hrs & died.

9/26/97 5025'-4929' Frac C/D sands as follows:  
141,000# 20/40 sand in 663 bbls Boragel Perfs broke back @ 2427 psi (13 BPM). Treated @ ave press os 2080 psi w/ave rate of 30.2 BPM. ISIP: 2810 psi, 5 min: 2773 psi. Flowback on 12/64" ck for 4-1/2 hrs & died.

PERFORATION RECORD

9/16/97	5724'-5737'	4 JSPF	52 holes
9/16/97	5790'-5798'	4 JSPF	32 holes
9/16/97	5831'-5839'	4 JSPF	32 holes
9/20/97	5454'-5469'	4 JSPF	60 holes
9/20/97	5474'-5482'	4 JSPF	32 holes
9/20/97	5485'-5492'	4 JSPF	28 holes
9/23/97	5232'-5238'	4 JSPF	24 holes
9/23/97	5310'-5323'	4 JSPF	52 holes
9/23/97	5356'-5363'	4 JSPF	28 holes
9/25/97	5025'-5039'	4 JSPF	56 holes
9/25/97	4916'-4929'	4 JSPF	52 holes

Cement top

Anchor @ 5695'

4916'-29'  
5025'-39'  
5232'-38'  
5310'-23'  
5356'-63'  
5454'-69'  
5474'-82'  
5485'-92'  
5724'-37'  
5790'-98'  
5831'-39'

SN @ 5760'  
EOT @ 5825'  
PBTD @ 5895'  
TD @ 5950''



Inland Resources Inc.

Tar Sands Federal #2-33

545 FNL 1991 FEL

NWNE Section 33-T8S-R17E

Duchesne Co, Utah

API #43-013-31867; Lease #U-76241

## Tar Sands Federal #7-33

Spud Date: 4/28/97  
 Put on Production: 11/22/97  
 GL: 5113' KB: 5126' (13'KB)

SURFACE CASING

CSG SIZE: 8-5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 7 jts. (290.48')  
 DEPTH LANDED: 288.56' GL  
 HOLE SIZE: 12-1/4"  
 CEMENT DATA: 120 sxs Premium cmt, est 8 bbls to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
 GRADE: J-55  
 WEIGHT: 15.5#  
 LENGTH: 137 jts. (5878')  
 HOLE SIZE: 7-7/8"  
 CEMENT DATA: 295 sxs Hibond mixed & 255 sxs thixotropic  
 CEMENT TOP AT: 26116  
 SET AT: 5877'

TUBING

SIZE/GRADE/WT.: 2-7/8" / M-50 / 6.5# @ 4,345'  
 NO. OF JOINTS: 139 jts  
 PACKER: 4,351'  
 SEATING NIPPLE: 2-7/8"  
 TOTAL STRING LENGTH: EOT @ 4,355'  
 SN LANDED AT: 4,348'

## Injection Wellbore Diagram

11/22/00 GBRIV

Cement top

Packer @ 4,351'

4406'-19'

5100'-07'

5181'-87'

5705'-08'

5711'-19'

5766'-70'

5772'-76'

SN @ 4,348'KB  
 EOT @ 4,355'KB  
 PBTD @ 5835'  
 TD @ 5877'

Sd Top @ 5820'  
 10/7/99

FRAC JOB

11/14/97 5705'-5776' Frac CP sand as follows:  
 95,300# 20/40 sand in 513 bbls of  
 Delta frac. Breakdown @ 2516 psi, treated  
 @ avg rate 28.1 bpm w/avg press of 1550  
 psi. ISIP-1791 psi, 5-min 1665 psi. Start  
 flowback on 12/64" ck for 3-1/2 hrs and  
 died.

11/17/97 5100'-5187' Frac B sand as follows:  
 115,300# of 20/40 sand in 555 bbls of  
 Delta frac. Breakdown @ 2340 psi.  
 Treated @ avg rate 26 bpm w/avg press  
 of 1730 psi. ISIP-2156 psi. 5-min 2027 psi.  
 Start flowback on 12/64" ck for 4 hrs &  
 died.

11/19/97 4406'-4419' Frac GB sand as follows:  
 88,300# of 20/40 sand in 457 bbls of  
 Delta frac. Breakdown @ 3024 psi.  
 Treated @ avg rate 24.1 bpm w/avg press  
 of 1800 psi. ISIP-2205 psi. 5-min 2137 psi.  
 Start flowback on 12/64" ck for 3 hrs &  
 died.



Inland Resources Inc.

Tar Sands Federal #7-33

1943 FNL 2009 FEL

SWNE Section 33-T8S-R17E

Duchesne Co, Utah

API #43-013-31860; Lease #U-77234

## Harbourtown Federal #21-33

Spud Date: 3/2/98  
 Put on Production: 4/13/98  
 GL: 5129' KB: 5142'

Initial Production: 74 BOPD,  
 40 MCFPD, ? BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
 GRADE:  
 WEIGHT:  
 LENGTH:  
 DEPTH LANDED: 299'  
 HOLE SIZE:  
 CEMENT DATA: 200 sxs cmt.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
 GRADE:  
 WEIGHT:  
 LENGTH:  
 DEPTH LANDED: 5909'  
 HOLE SIZE:  
 CEMENT DATA: 510 sks  
 CEMENT TOP AT: ABOVE 11000  
 6000' in CB

TUBING

SIZE/GRADE/WT.: 2-7/8"  
 NO. OF JOINTS: ? 5737'  
 TUBING ANCHOR:  
 SEATING NIPPLE:  
 TOTAL STRING LENGTH:  
 SN LANDED AT:

SUCKER RODS

POLISHED ROD:  
 SUCKER RODS:  
 TOTAL ROD STRING LENGTH:  
 PUMP NUMBER:  
 PUMP SIZE:  
 STROKE LENGTH:  
 PUMP SPEED, SPM:  
 LOGS: DIGL/SP/GR/CAL  
 SDL/DSN/GR


FRAC JOB

SWFR (5688'-32')	426 bbls 70,500 lbs sand, 20/40 sd x-link gelled water.
SWFR (5334'-41')	305 bbls 40,700 lbs sand, 20/40 sd x-link gelled water.
SWFR (5020'-5112')	532 bbls 100,000 lbs sand, 20/40 sd x-link gelled water.

Well was drilled by Rosewood.

It is a non-unit well (fee?).

No further information available.

PERFORATION RECORD

Inland Resources Inc.

Harbourtown Federal #21-33

513 FNL 1938 FWL

NENW Section 33-T8S-R17E

Duchesne Co, Utah

API #43-013-31914



## ATTACHMENT E

### NAME AND DEPTH OF USDWs

**For Class II wells, submit geologic name and depth to bottom of all underground sources of drinking water, which may be affected by the injection.**

Due to the location and depth of the well, it will not affect any source of drinking water. See Attachments E-1 through E-2, showing pertinent water analyses.

Attachment E-1 Analysis of the formation water taken from the Tar Sands Federal #15-28-8-17.

Attachment E-2 Analysis of the compatibility of the injected and formation water

**UNICHEM**

A Division of BJ Services

P.O. Box 217  
Roosevelt, Utah 84066Office (435) 722-6066  
Fax (435) 722-5727

Attachment E-1

**WATER ANALYSIS REPORT**

Company INLAND PRODUCTION Address \_\_\_\_\_ Date 2/27/01  
 Source Tar Sands 15-28-8-17 Date Sampled 2/26/01 Analysis No. \_\_\_\_\_

	Analysis	mg/l(ppm)	*Meg/l
1. PH	<u>9.1</u>		
2. H <sub>2</sub> S (Qualitative)	<u>0.5</u>		
3. Specific Gravity	<u>1.018</u>		
4. Dissolved Solids		<u>19,638</u>	
5. Alkalinity (CaCO <sub>3</sub> )	CO <sub>3</sub>	<u>0</u>	÷ 30 <u>0</u> CO <sub>3</sub>
6. Bicarbonate (HCO <sub>3</sub> )	HCO <sub>3</sub>	<u>732</u>	÷ 61 <u>12</u> HCO <sub>3</sub>
7. Hydroxyl (OH)	OH	<u>0</u>	÷ 17 <u>0</u> OH
8. Chlorides (Cl)	Cl	<u>11,300</u>	÷ 35.5 <u>319</u> Cl
9. Sulfates (SO <sub>4</sub> )	SO <sub>4</sub>	<u>0</u>	÷ 48 <u>0</u> SO <sub>4</sub>
10. Calcium (Ca)	Ca	<u>16</u>	÷ 20 <u>1</u> Ca
11. Magnesium (Mg)	Mg	<u>0</u>	÷ 12.2 <u>0</u> Mg
12. Total Hardness (CaCO <sub>3</sub> )		<u>40</u>	
13. Total Iron (Fe)		<u>2.0</u>	
14. Manganese			
15. Phosphate Residuals			

\*Milli equivalents per liter

**PROBABLE MINERAL COMPOSITION**

	Compound	Equly. Wt.	X	Meg/l	=	Mg/l
1	Ca(HCO <sub>3</sub> ) <sub>2</sub>	81.04	<u>1</u>			<u>81</u>
0	CaSO <sub>4</sub>	68.07				
	CaCl <sub>2</sub>	55.50				
	Mg(HCO <sub>3</sub> ) <sub>2</sub>	73.17				
	MgSO <sub>4</sub>	60.19				
	MgCl <sub>2</sub>	47.82				
	NaHCO <sub>3</sub>	84.00	<u>11</u>			<u>924</u>
	Na <sub>2</sub> SO <sub>4</sub>	71.03				
	NaCl	58.46	<u>319</u>			<u>18,649</u>

Saturation Values	Distilled Water 20°C
CaCO <sub>3</sub>	13 Mg/l
CaSO <sub>4</sub> · 2H <sub>2</sub> O	2,090 Mg/l
MgCO <sub>3</sub>	103 Mg/l

REMARKS \_\_\_\_\_

Received Time-Mar. 1.-10:45AM

## AQUAMIX SCALING PREDICTIONS

COMPANY: INLAND PRODUCTION CO  
 LOCATION:  
 SYSTEM:

2-28-2001

WATER DESCRIPTION:	JOHNSON WATER	T.S. 15-25-8-17
P-ALK AS PPM CaCO3	0	0
M-ALK AS PPM CaCO3	393	1200
SULFATE AS PPM SO4	130	0
CHLORIDE AS PPM Cl	71	11300
HARDNESS AS PPM CaCO3	0	0
CALCIUM AS PPM CaCO3	180	40
MAGNESIUM AS PPM CaCO3	169	0
SODIUM AS PPM Na	46	7590
BARIUM AS PPM Ba	0	0
STRONTIUM AS PPM Sr	0	0
CONDUCTIVITY	0	0
TOTAL DISSOLVED SOLIDS	600	19638
TEMP (DEG-F)	100	100
SYSTEM pH	7.4	9.1

## WATER COMPATIBILITY CALCULATIONS

JOHNSON WATER AND T.S. 15-25-8-17

CONDITIONS: pH=8.3. TEMPERATURE ESTIMATED FROM COMPONENT WATERS.

WATER ONE IS JOHNSON WATER

% Water 1	STIFF DAVIS CaCO3 INDEX	lbs/1000 BBL EXCESS CaCO3	mg/l BaSO4 IN EXCESS OF SATURATION	mg/l SrO4 IN EXCESS OF SATURATION	mg/l Gypsum IN EXCESS OF SATURATION
100	1.23	56	0	0	0
90	1.17	52	0	0	0
80	1.10	47	0	0	0
70	1.01	42	0	0	0
60	.92	37	0	0	0
50	.81	31	0	0	0
40	.70	26	0	0	0
30	.62	21	0	0	0
20	.53	16	0	0	0
10	.41	11	0	0	0
0	.27	6	0	0	0

## ATTACHMENT G

### GEOLOGICAL DATA ON INJECTION AND CONFINING ZONES

**For Class II wells, submit appropriate geological data on the injection zone and confining zones, including lithologic description, geological name, thickness, and depth and fracture pressure.**

The proposed injection well produced from and will inject into the Green River formation. Water is sourced from the Johnson Water District and injected or is commingled with produced water at the Monument Butte Injection Facility and processed for individual well injection.

The injection zones are in the Green River formation, bounded by the Garden Gulch marker and the Basal Carbonate Marker. The Green River is composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shales. At the Tar Sands Federal #15-28-8-17 location, the proposed injection zone is from 4969'-5944'. The porous and permeable lenticular sandstones vary in thickness from 0' – 31' and are confined to the Monument Butte area by low porosity calcareous shales and carbonates.

The confining strata directly above and below the injection zones are the top of the Garden Gulch formation and the Basal Carbonate, in the Tar Sands Federal #15-28-8-17 well. The strata confining the injection zone are composed of tight, moderately calcareous, sandy lacustrine shales. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

The fracture pressure of the Tar Sands Federal #15-28-8-17 will be determined upon testing. The minimum fracture gradient calculates at 0.706 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be conducted upon injection and periodically thereafter to determine the actual fracture pressure. As the fracture pressure increases, we may elect to increase the injection pressure, but will not exceed the maximum of 1563 psig.

#### Communication Prevention:

The injection system will be equipped with high and low pressure shut down devices, which will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.

Attachment G-1	Formation Tops
Attachment G-2	Proposed Maximum Injection Pressure
Attachment G-3	Fracture Reports Dated 9/14/00
Attachment G-4	Drilling and Completion Reports Dated 8/11/00 THROUGH 8/18/00, AND 9/13/00 THROUGH 9/20/00


ATTACHMENT G-1  
FORMATION TOPS  
TAR SANDS FEDERAL #15-28-8-17

<u>FORMATION</u>	<u>DEPTH (ft)</u>
Green River	3934'
Garden Gulch	4240'
Point Three Marker	4511'
X Marker	4748'
Y-Marker	4775'
Douglas Creek	4904'
Bicarbonate Marker	5196'
B-Limestone	5330'
Castle Peak Limestone	5746'
Total Depth	6125'

Attachment "G-2"

**Tar Sands Federal #15-28-8-17  
Proposed Maximum Injection Pressure**

Frac Interval (feet)		Avg. Depth (feet)	ISIP (psi)	Calculated Frac Gradient (psi/ft)	Pmax
Top	Bottom				
4969	5000	4985	3100	1.055	3080
5244	5285	5265	2030	0.819	2011
5765	5944	5855	1600	0.706	1563
				<b>Minimum</b>	<u>1563</u>



Calculation of Maximum Surface Injection Pressure

$P_{max} = (\text{Frac Grad} - (0.433 \times 1.005)) \times \text{Depth of Top Perf}$

where pressure gradient for the fresh water is .433 psi/ft and  
specific gravity of the injected water is 1.005.

$\text{Frac Gradient} = (\text{ISIP} + (0.433 \times \text{Avg. Depth})) / \text{Avg. Depth}$



Attachment G-3  
Page 1 of 3

### DAILY COMPLETION REPORT

WELL NAME: Tar Sands Federal 15-28-8-17

Report Date: 9/15/00

Completion Day: 03(a)

Present Operation: Perf/frac B sands

Rig: KES #965

#### WELL STATUS

Surf Csg: 8 5/8 @ 307'

Prod Csg: 4 1/2" 11.6# @ 6110'

Csg PBDT: 6046'

Tbg: Size: 2 3/8 Wt: 4.7#

Grd: J-55 Pkr/EOT @: 0

BP/Sand PBDT: 6046'

#### PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
CP1 sds	5765-5771'	1/6			
CP1 sds	5791-5802'	1/11			
CP2 sds	5824-5828'	1/4			
CP2 sds	5831-5834'	1/3			
CP3 sds	5921-5944'	2/46			

#### CHRONOLOGICAL OPERATIONS

Date Work Performed: 14-Sep-00

SITP: 0 SICP: 0

RU BJ Services "Ram head" flange. RU BJ and frac CP sds W/ 120,000# 20/40 sand in 721 bbls Viking I-25 fluid. Perfs broke back @ 3550 psi @ 11 BPM. Treated @ ave press of 2000 psi W/ ave rate of 34 BPM. ISIP-1600 psi, 5 min-1495 psi. Leave pressure on well. Est 850 BWTR (includes 129 bbls ahead of frac). ✓

See day 3(b)

#### FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 129

Starting oil rec to date: 0

Fluid lost/recovered today: 721

Oil lost/recovered today: 0

Ending fluid to be recovered: 850

Cum oil recovered: 0

IFL: 0 FFL: 0 FTP: 0 Choke: 0 Final Fluid Rate: 0 Final oil cut: 0

#### STIMULATION DETAIL

Base Fluid used: Viking I-25 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail:

7000 gals of pad

3000 gals W/ 1-5 ppg of 20/40 sand

14000 gals W/ 5-8 ppg of 20/40 sand

2614 gals W/ 8 ppg of 20/40 sand

Flush W/ 3654 gals of slick water

#### COSTS

KES rig \$617

BOP \$130

BJ Services-CP sds \$34,892

Frac water \$700

IPC Supervision \$100

Max TP: 2750 Max Rate: 35 BPM Total fluid pmpd: 721 bbls

Avg TP: 2000 Avg Rate: 34 BPM Total Prop pmpd: 120,000#

ISIP: 1600 5 min: 1495 10 min: 0 15 min: 0

Completion Supervisor: Gary Dietz

DAILY COST: \$36,439

TOTAL WELL COST: \$211,418



Attachment G-3  
Page 2 of 3

### DAILY COMPLETION REPORT

WELL NAME: Tar Sands Federal 15-28-8-17 Report Date: 9/15/00 Completion Day: 03(b)  
Present Operation: Perf/frac/flowback D sds Rig: KES #965

#### WELL STATUS

Surf Csg: 8 5/8 @ 307' Prod Csg: 4 1/2" 11.6# @ 6110' Csg PBTD: 6046'  
Tbg: Size: 2 3/8 Wt: 4.7# Grd: J-55 Pkr/EOT @: 0 BP/Sand PBTD: 5500'

#### PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
B2 sds	5244-5265'	2/42	CP1 sds	5765-5771'	1/6
B2 sds	5267-5285'	2/36	CP1 sds	5791-5802'	1/11
			CP2 sds	5824-5828'	1/4
			CP2 sds	5831-5834'	1/3
			CP3 sds	5921-5944'	2/46

#### CHRONOLOGICAL OPERATIONS

Date Work Performed: 14-Sep-00 SITP:  SICP: 1495

RU Schlumberger and set HE RBP @ 5500'. Bleed pressure off well. Rec 2 BW. Perf B2 sds @ 5244-65' & 5267-85' W/ 2 JSPF. RU BJ Services and frac B2 sds W/ 78,000# 20/40 sand in 469 bbls Viking I-25 fluid. Perfs broke dn @ 2160 psi. Treated @ ave press of 1800 psi W/ ave rate of 30 BPM. ISIP-2030 psi, 5 min-1900 psi. Leave pressure on well. Est 1317 BWTR.

See day 3(c)

#### FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 850 Starting oil rec to date: 0  
Fluid lost/recovered today: 467 Oil lost/recovered today:   
Ending fluid to be recovered: 1317 Cum oil recovered: 0  
IFL:  FFL:  FTP:  Choke:  Final Fluid Rate:  Final oil cut:

#### STIMULATION DETAIL

Base Fluid used: Viking I-25 Job Type: Sand frac  
Company: BJ Services

Procedure or Equipment detail:

4000 gals of pad  
2000 gals W/ 1-5 ppg of 20/40 sand  
8000 gals W/ 5-8 ppg of 20/40 sand  
2390 gals W/ 8 ppg of 20/40 sand  
Flush W/ 3318 gals of slick water

#### COSTS

KES rig	\$617
RBP rental	\$600
BJ Services-B sds	\$14,566
Frac water	\$500
Schlumberger-B sds	\$3,245
IPC Supervision	\$100

Max TP: 2702 Max Rate: 30 BPM Total fluid pmpd: 469 bbls  
Avg TP: 1800 Avg Rate: 30 BPM Total Prop pmpd: 78,000#  
ISIP: 2030 5 min: 1900 10 min:  15 min:   
Completion Supervisor: Gary Dietz

DAILY COST: \$19,628  
TOTAL WELL COST: \$231,046





Attachment G-3  
Page 3 of 3

### DAILY COMPLETION REPORT

WELL NAME: Tar Sands Federal 15-28-8-17

Report Date: 9/15/00

Completion Day: 03(c)

Present Operation: Pull plugs / C/O PBTD

Rig: KES #965

#### WELL STATUS

Surf Csg: 8 5/8 @ 307'  
Tbg: Size: 2 3/8 Wt: 4.7#

Prod Csg: 4 1/2" 11.6# @ 6110'  
Grd: J-55 Pkr/EOT @: 0

Csg PBTD: 6046'  
BP/Sand PBTD: 5500'  
BP/Sand PBTD: 5060'

#### PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
D2 sds	4969-4978'	4/36	CP1 sds	5765-5771'	1/6
D2 sds	4995-5000'	4/20	CP1 sds	5791-5802'	1/11
B2 sds	5244-5265'	2/42	CP2 sds	5824-5828'	1/4
B2 sds	5267-5285'	2/36	CP2 sds	5831-5834'	1/3
			CP3 sds	5921-5944'	2/46

#### CHRONOLOGICAL OPERATIONS

Date Work Performed: 14-Sep-00

SITP:            SICP: 1900

RU Schlumberger and set HE RBP @ 5060'. Bleed pressure off well. Rec 2 BW. Perf D2 sds @ 4969-78' & 4995-5000' W/ 4 JSPF. RU BJ Services and frac D2 sds W/ 57,080# 20/40 sand in 356 bbls Viking I-25 fluid. Perfs broke dn @ 3980 psi. Treated @ ave press of 2400 psi W/ ave rate of 30.5 BPM. ISIP-3100 psi, 5 min-2710 psi. RD BJ & WLT. Flowback D sds frac on 12/64 choke for 2 1/2 hrs & died. Rec 77 BTF (est 22% of frac load). SIFN W/ est 1594 BWTR.

#### FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1317 Starting oil rec to date: 0  
Fluid lost/recovered today: 277 Oil lost/recovered today:             
Ending fluid to be recovered: 1594 Cum oil recovered: 0  
IFL:            FFL:            FTP:            Choke: 12/64 Final Fluid Rate:            Final oil cut:           

#### STIMULATION DETAIL

Base Fluid used: Viking I-25 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail:

2000 gals of pad

1000 gals W/ 1-5 ppg of 20/40 sand

5500 gals W/ 5-8 ppg of 20/40 sand

3286 gals W/ 8 ppg of 20/40 sand

Flush W/ 3150 gals of slick water

#### COSTS

KES rig	\$617
RBP rental	\$600
BJ Services-D sds	\$10,494
Frac water	\$500
Schlumberger-D sds	\$1,551
Frac head rental	\$200
Frac tks (5 X 3 days)	\$150
IPC Supervision	\$100

Max TP: 3663 Max Rate: 30.5 BPM Total fluid pmpd: 356 bbls

Avg TP: 2400 Avg Rate: 30.5 BPM Total Prop pmpd: 57,080#

ISIP: 3100 5 min: 2710 10 min:            15 min:           

Completion Supervisor: Gary Dietz

DAILY COST: \$14,212

TOTAL WELL COST: \$245,258



## DAILY DRILLING REPORT

Attachment G-4  
Page 1 of 6

PTS FED 15-28

SW/SE Section 28 - T8S - R17E

Duchesne Co., UT

API # 43-013-32109

Spud Dat

TD

Drig Rig UNION 314

Report Date 8/11/00 Days Since Spud 1 Depth: 250 Footage 250'

Time	Operation
0.00 HRS	MIRU Union #14 & set equipment on 08/07/00. REPAIR DRAW WORKS
1.00 HRS	Drill MH & RH. SPUD WELL @ 8:15 P.M. ON 08/10/00
1.25 HRS	Drill 23' of 17-1/2" hole. Set conductor pipe
1.00 HRS	NU flow line and air bowl
6.50 HRS	Drill 12-1/4" hole to 250'

Daily Cost \$9,820 Cumulative Cost \$9,820

Report Date 8/12/00 Days Since Spud 2 Depth: 666 Footage 416'

Time	Operation
1.50 HRS	Drill 7-7/8" hole f/ 250' to 325'
0.50 HRS	C & C hole
1.50 HRS	TOH & work tight hole
1.50 HRS	PU & TIH w/ 8-5/8" GS & 7 jts 8-5/8" 24# j-55 csg. Landed @ 307'. RU BJ Services
0.00 HRS	and cmt csg as follows: 20 bbls dye wtr, 20 bbls gel wtr, 141 sx Class G cmt w/ 2%
0.00 HRS	CaCL2, 1/4#/sx cello-flake mixed @ 15.8 ppg w/ 1.17 cf/sx yld. Had good returns
0.00 HRS	w/ 4 bbls cmt tosfc. Plug was down @ 11:00 a.m. 08/11/00. RD BJ.
4.50 HRS	WOC
2.25 HRS	NU BOP stack & choke manifold
2.75 HRS	Pressure test BOP, kelly, kelly cock & choke to 2000 psi. Test sfc csg to 1500 psi
2.00 HRS	TIH w/ bit #3 & BHA. Drill cmt, plug & shoe
4.25 HRS	Drill 7-7/8" hole f/ 325' to 544'. Survey - 3/4 @ 504'
1.25 HRS	Drill 7-7/8" hole f/ 544' to 635'
1.00 HRS	Change out air rubber. Install drivers. Change over to DP
1.00 HRS	Drill 7-7/8" hole f/ 635' to 666'

Daily Cost \$7,376 Cumulative Cost \$17,196

Report Date 8/13/00 Days Since Spud 3 Depth: 2230 Footage 1564'

Time	Operation
4.75 HRS	Drill 7-7/8" hole w/ air mist to a depth of 1067'
0.75 HRS	Rig service & survey
7.00 HRS	Drill 7-7/8" hole w/ air mist to a depth of 1559
0.25 HRS	Rig service & survey
7.75 HRS	Drill 7-7/8" hole w/ air mist to a depth of 2053'
0.50 HRS	Rig service & survey
3.00 HRS	Drill 7-7/8" hole w/ air mist to a depth of 2230'



## DAILY DRILLING REPORT

Attachment G-4  
Page 2 of 6

Daily Cost \$17,717 Cumulative Cost \$34,913

Report Date	8/14/00	Days Since Spud	4	Depth:	3258	Footage	1028'
Time	Operation						
2.00	HRS	Drill 7-7/8" hole w/ air mist to a depth of 2362'					
1.00	HRS	Rig service					
1.75	HRS	R & R air compressor					
0.50	HRS	Drill 7-7/8" hole w/ air mist to a depth of 2393'					
3.50	HRS	R & R air compressor					
2.75	HRS	Drill 7-7/8" hole w/ air mist to a depth of 2577'					
0.25	HRS	Rig service & survey					
7.75	HRS	Drill 7-7/8" hole w/ air mist to a depth of 3073'					
0.50	HRS	Rig service & survey					
4.00	HRS	Drill 7-7/8" hole w/ air mist to a depth of 3258'					

Daily Cost \$12,664 Cumulative Cost \$47,577

Report Date	8/15/00	Days Since Spud	5	Depth:	4082	Footage	824'
Time	Operation						
1.00	HRS	Drill 7-7/8" hole w/ air mist to a depth of 3350'					
1.50	HRS	Rig service					
3.50	HRS	Drill 7-7/8" hole w/ air mist to a depth of 3565'					
0.50	HRS	Survey					
3.50	HRS	Drill 7-7/8" hole w/ air mist to a depth of 3815'					
1.25	HRS	C & C hole, load w/ water, break circulation					
2.50	HRS	TOH w/ drill string & BHA					
0.25	HRS	Rig service					
3.00	HRS	TIH w/ #4 fluid bit & BHA					
0.50	HRS	Break circulation, wash 30' to BTM					
5.50	HRS	Drill 7-7/8" hole w/ fluid to a depth of 4082'					

Daily Cost \$16,851 Cumulative Cost \$64,428

Report Date	8/16/00	Days Since Spud	6	Depth:	4961	Footage	879'
Time	Operation						
1.00	HRS	Rig service & survey					
12.25	HRS	Drill 7-7/8" hole w/ fluid to a depth of 4575'					
0.50	HRS	Rig service & survey					
6.75	HRS	Drill 7-7/8" hole w/ fluid to a depth of 4876'					
0.25	HRS	Rig service					
3.25	HRS	Drill 7-7/8" hole w/ fluid to a depth of 4961'					

Daily Cost \$18,960 Cumulative Cost \$83,388



Attachment G-4  
Page 3 of 6

## DAILY DRILLING REPORT

Report Date 8/17/00 Days Since Spud 7 Depth: 5810 Footage 849'

Time	Operation
2.75 HRS	Drill 7-7/8" hole w/ fluid to a depth of 5072'
1.50 HRS	Rig service & survey
6.50 HRS	Drill 7-7/8" hole w/ fluid to a depth of 5350'
0.25 HRS	Rig service
6.00 HRS	Drill 7-7/8" hole w/ fluid to a depth of 5556'
0.75 HRS	Rig service & survey
6.25 HRS	Drill 7-7/8" hole w/ fluid to a depth of 5810'

Daily Cost \$10,779 Cumulative Cost \$94,167

Report Date 8/18/00 Days Since Spud 8 Depth: 6119 Footage 309'

Time	Operation
1.50 HRS	Drill 7-7/8" hole w/ fluid to a depth of 5820'
1.25 HRS	Rig service
6.75 HRS	Drill 7-7/8" hole w/ fluid to a depth of 6119'. TD @ 3:30 p.m. on 08/17/00
5.50 HRS	C & C hole. Drop survey. Lay dn drill string & BHA
11.00 HRS	RU loggers & run Dual Induction/Guard log/SP compensated density
0.00 HRS	Neutron Gamma ray/ Caliper log. PSI broke dn 6 hrs Rig time owed
3.25 HRS	PU & MU 4-1/2" guide shoe, 1 jt float collar 143 jts 15.5# J-55 csg @ 6109.84' KB
1.50 HRS	Cement as follows: 20 bbls dye, 20 bbls Mud Clean II
0.00 HRS	360 sx Prem Lite II w/ 10% Gel & 3% KCL mixed @ 11 ppg > 3.43 YLD
0.00 HRS	625 sx 50/50 Poz w/ 2% Gel & 3% KCL mixed @ 14.4 ppg > 1.24 YLD
0.00 HRS	Plug was down @ 1:23 p.m. on 08/18/00
1.50 HRS	ND BOPs Drop slips w/ 57,000# string weight
3.00 HRS	Clean & dump pits. Release rig @ 4:30 p.m. on 08/18/00.

Daily Cost \$52,714 Cumulative Cost 146,881



Attachment G-4  
Page 4 of 6

## SUMMARY WORKOVER REPORT

**PTS FED 15-28**

SW/SE Section 28 - T8S - R17E  
Duchesne Co., UT  
API # 43-013-2109

Spud Dat 8/10/00  
TD

Completion or Workover Rig KES #965

**Report Date 9/13/00 Day 1**

**Perf/breakdn CP sands**

**Date Work Performed 9/12/00**

MIRU KES RIG #965. Install 4-1/2" x 5-1/2" bushing & 5M frac head. NU 5 M BOP. Press test csg, blind rams, csg valves & frac head seal to 3000 psi. Tally, drift, PU & TIH w/ 3-7/8" bit, 4-1/2" csg scraper & 110 jts 2-3/8" 8rd 4.7# J-55 tbg to 3274'. SIFN.

Daily Cost 168,269 Cumulative Cost 168,269

**Report Date 9/14/00 Day 2**

**Frac CP, B, & D sds, FB D sds**

**Date Work Performed 9/13/00**

Con't PU & TIH w/ bit, scraper, and 2-3/8" J-55 tbg (185 jts total). Tag PBTD @ 6046'. TBG displaced 14 BW on TiH. TOH w/ tbg. LD bit & scraper. RU Schlumberger and perf CP sds @ 5765'-71', 5791'-5802', 5824'-28', 5831'-34' (1 JSPF) & 5291'-244' (2 JSPF). RD WLT TIH w/ 4-1/2" HD pkr & tbg. Set pkr @ 5877'. Breakdn perfs 5921'-44' (dn tbg) @ 2900 psi. Establish inj rate of 2.1 BPM @ 1800 psi. Breakdn perfs 5765' - 5834' (dn csg) @ 2700 psi. Est inj rate of 2.1 BPM @ 1300 psi. Lost 2 BW. Release pkr. TOH w/ tbg. SIFN w/ est 129 BWTR.

Daily Cost \$6,710 Cumulative Cost 174,979

**Report Date 9/15/00 Day 3**

**Perf/frac B Sands**



Attachment G-4  
Page 5 of 6

## SUMMARY WORKOVER REPORT

Date Work Performed 9/14/00

RU BJ Services "Ram Head" flange. RU BJ and frac CP sds w/ 120,000# 20/40 sand in 721 bbls Viking I-25 Fluid. Perfs broke back @ 3550 psi @ 11 BPM. Treated @ avg press of 2000 psi w/ avg rate of 34 BPM. ISIP: 1600 psi, 5 min: 1495 psi. Leave press on well. Est 850 BWTR (includes 129 bbls ahead of frac).

### STIMULATION DETAIL: CP SANDS

7000 gals of pad

3000 gals w/ 1-5 ppg of 20/40 sand

14,000 gals w/ 5-8 ppg of 20/40 sand

2614 gals w/ 8 ppg of 20/40 sand

Flush w/ 3654 gals of slick wtr

Max TP: 2750, Avg TP: 2000, Max Rate: 35 BPM, Avg Rate: 34 BPM

Total fluid pmpd: 721 bbls, Total Prop pmpd: 120,000#

ISIP: 1600, 5 min: 1495

RU Schlumberger and set HE RBP @ 5500'. Bleed press off well. Rec 2 BW. Perf B2 sds @ 5244'-5265' & 5267' - 5285' w/ 2 JSPF. RU BJ Services & frac B2 Sds w/ 78,000# 20/40 sd in 469 bbls Viking I-25 Fluid. Perfs broke dn @ 2160 psi. Treated @ avg press of 1800 psi w/ avg rate of 30 BPM. ISIP: 2030 psi, 5 min: 1900 psi. Left press on well. Est 1317 BWTR.

### STIMULATION DETAIL: B2 SANDS

4000 gals of pad

2000 gals w/ 1-5 ppg of 20/40 sand

8000 gals w/ 5-8 ppg of 20/40 sand

2390 gals w/ 8 ppg of 20/40 sand

Flush w/ 3318 gals of slick water

Max TP: 2702, Avg TP: 1800, Max Rate: 30 BPM, Avg Rate: 30 BPM

total fluid pmpd: 469 bbls, Total Prop pmpd: 78,000#

ISIP: 2030, 5 min: 1900

RU Schlumberger and set HE RBP @ 5060'. Bled press off well. Rec 2 BW. Perf D2 Sands @ 4969' - 4978' & 4995' - 5000' w/ 4 JSPF. RU BJ Services & frac D2 sds w/ 57,080# 20/40 sand in 356 bbls Viking I-25 Fluid. Perfs broke dn @ 3980 psi. Treated @ avg press of 2400 psi w/ avg rate of 30.5 BPM. ISIP: 3100 psi, 5 min: 2710 psi. RD BJ & WLT. Flowback D sds frac on 12/64" choke fo 2.5 hrs & died. Rec 77 BTF (est 22% of frac load). SIFN w/ est 1594 BWTR.

### STIMULATION DETAIL: D2 SANDS

2000 gals of pad

1000 gals w/ 1-5 ppg of 20/40 sand

5500 gals w/ 5-8 ppg of 20/40 sand

3286 gals w/ 8 ppg of 20/40 sand

Flush w/ 3150 gals of slick water

Max TP: 3663, Avg TP: 2400, Max Rate: 30.5 BPM, Avg Rate: 30.5 BPM

Total fluid pmpd: 356 bbls, Total pmpd: 57,080 #

ISIP: 3100, 5 min: 2710

---

Daily Cost \$70,279 Cumulative Cost 245,258

Report Date 9/16/00 Day 4

Swabbing

Date Work Performed 9/15/00

SIP: 20 psi. TIH w/ RH & tbg. Tag sd @ 4835'. Circ sd out to RBP @ 5060'. Release plg. TOH w/ tbg. LD plg. TIH w/ RH & tbg. Tag sd @ 5406'. Circ sd out to RBP @ 5500'. Release plg. TOH w/ tbg. LD plg. TIH w/ NC & tbg. Tagged sd @ 5941'. C/O sd to PBTB @ 6046'. Lost 39 BW during circ. Pull EOT to 5976'. RU swab equip. IFL @ sfc. Made 4 swab runs rec 59 BTF w/ 0% OC. FFL @ 500'. SWIFN. Est 1133 BWTR.



Attachment G-4  
Page 6 of 6

## SUMMARY WORKOVER REPORT

---

Daily Cost \$2,787 Cumulative Cost 248,045

**Report Date** 9/18/00 **Day** 5

**Swabbing**

**Date Work Performed** 9/16/00

20 psi csg. 20 psi tbg. RU swab equip. Made 23 swab runs. IFL @ sfc. FFL @ 1100'. Avg fluid level: 800'. Trace of sd first 12 runs. Rec: 35.2 BO & 312 BW.

---

Daily Cost \$2,293 Cumulative Cost 250,338

**Report Date** 9/19/00 **Day** 6

**TIH w/ Production**

**Date Work Performed** 9/18/00

50 psi csg, 70 psi tbg. RU swab equip. Made 3 swab runs. IFL @ surface. FFL @ 700'. No sand in fluid. Rec 11.4 BO & 18.3 BW. Circ well clean. TIH w/ 3 jts & tag @ 6043. LD excess tbg. TOH w/ tbg & BHA. TIH w/ production string listed below. RD tbg equip. Strip off frac head installprod head. Set TAC w/ 13,000# tension. RU tbg equip. Lost 140 BW. SWIFN.

---

Daily Cost \$2,385 Cumulative Cost 252,723

**Report Date** 9/20/00 **Day** 7

**Well on Production**

**Date Work Performed** 9/19/00

Flush tbg w/ 35 BW @ 250 deg F. TIH w/ rod string. Seat pmp space out. Fill tbg w/ 5 bbls test to 700 psi. Hang off rods & RU pmpg unit. POP @ 1:00 p.m. 09/19/00 @ 73" Stroke, 7 SPM. Lost 35 BW.

---

Daily Cost \$85,461 Cumulative Cost 338,184

ATTACHMENT H  
OPERATING DATA

Submit the following proposed operating data for each well (including all those to be covered by area permits): (1) average and maximum daily rate and volume of the fluids to be injected; (2) average and maximum injection pressure; (3) nature of annulus fluid; and (4) for Class II wells, source and analysis of the physical and chemical characteristics of the injection fluid.

1. Estimated average daily rate is 300 BPD, and the estimated maximum daily rate is 500 BPD.
2. The average and maximum surface pressure will be determined upon testing.
3. Fresh water treated with scale inhibitor, oxygen scavenger, biocide (behind packer fluid).
4. The injected fluid is primarily culinary water from the Johnson Water District; in secondary cases the injected fluid will be culinary water from the Johnson Water District commingled with produced water. (See Attachments E-1 through E-4 for analysis).



**ATTACHMENT M**  
**CONSTRUCTION DETAILS**

**Submit schematic or other appropriate drawings of the surface and subsurface construction details of the well.**

Attachment M-1	Wellbore schematic of Tar Sands Federal #15-28-8-17
Attachment M-2	Site Plan of Tar Sands Federal #15-28-8-17

## Tar Sands Federal #15-28

Spud Date: 8/10/00  
Put on Production: 9/19/00  
GL: 5132' KB: 5142'

Initial Production: 115 BOPD,  
75 MCFPD, 26 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 311' (7 jts)  
DEPTH LANDED: 307.16' GL  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 141 sx Class "G" cement plus additives

PRODUCTION CASING

CSG SIZE: 4-1/2"  
GRADE: J-55  
WEIGHT: 11.6#  
LENGTH: 144 jts (6113.84')  
DEPTH LANDED: 6109.84'  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 360 sx PremLite II; followed by 625 sx 50/50 Pozmix.

TUBING

SIZE/GRADE/WT.: 2-3/8" / J-55 / 6.5#  
NO. OF JOINTS: 183 jts  
TUBING ANCHOR: 5884'  
SEATING NIPPLE: 2-3/8" (1.10')  
TOTAL STRING LENGTH: EOT @ 5987.08' KB  
SN LANDED AT: 5952.92' KB

SUCKER RODS

POLISHED ROD: 1-1/4" x 22' polished  
SUCKER RODS: 4 - 1-1/2" weight rods; 10 - 3/4" scraped; 134 - 3/4" plain;  
89 - 3/4" scraped; and 1 each of 3/4" x 8', 3/4" x 6' and 3/4" x 2' pony rods.  
TOTAL ROD STRING LENGTH: ?  
PUMP SIZE: 2-1/2 x 1-1/2 x 16' RHAC pump  
STROKE LENGTH: 73"  
PUMP SPEED, SPM: 7  
LOGS: GR, SP, Spectral Density-Dual Spaced Neuron, CBL-GR

FRAC JOB


9/14/00 5765'-5944' Frac CP sand as follows:  
120,000# 20/40 sand in 721 bbls Viking I-25 fluid. Perfs broke down @ 3550 psi. Treated @ avg press of 2000 psi w/avg rate of 34 BPM. ISIP-1600 psi, 5-min 1495 psi. Left pressure on well.

9/14/00 4969'-5000' Frac D-2 sand as follows:  
57,080# 20/40 sand in 356 bbls Viking I-25 fluid. Perfs broke down @ 3980 psi. Treated @ avg press of 2400 psi w/avg rate of 30.5 BPM. ISIP-3100 psi, 5-min 2710 psi. Flowback on 12/64" choke for 2-1/2 hours and died. Rec 77 BTF.

9/14/00 5244'-5285' Frac B-2 sand as follows:  
78,000# 20/40 sand in 469 bbls Viking I-25 fluid. Perfs broke down @ 2160 psi. Treated @ avg press of 1800 psi w/avg rate of 30 BPM. ISIP-2030 psi, 5-min 1900 psi. Left pressure on well.

PERFORATION RECORD

9/14/00	4969'-4978'	4 JSPF	36 holes
9/14/00	4995'-5000'	4 JSPF	20 holes
9/14/00	5244'-5265'	2 JSPF	42 holes
9/14/00	5267'-5285'	2 JSPF	36 holes
9/13/00	5765'-5771'	1 JSPF	6 holes
9/13/00	5791'-5802'	1 JSPF	11 holes
9/13/00	5824'-5828'	1 JSPF	4 holes
9/13/00	5831'-5834'	1 JSPF	3 holes
9/13/00	5921'-5944'	2 JSPF	46 holes



Inland Resources Inc.

Tar Sands Federal #15-28

518 FSL 1890 FEL

SWSE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32109; Lease #U-76241

# Inland Production Company Site Facility Diagram

Tar Sands Federal 15-28-8-17

SWSE Sec. 28, T8S, 17E

Duchesne County, Utah

UTU-76241

Site Security Plan is held at the Pleasant Valley  
Office, Duchesne County Utah

## Production Phase:


- 1) Valves 1, 3, 4 sealed closed
- 2) Valves 2, 5, 6 sealed open

## Sales Phase:

- 1) Valves 1, 2, 4, 5, 6 sealed closed
- 2) Valves 3 open

## Draining Phase:

- 1) Valve 1 open



**ATTACHMENT Q**  
**PLUGGING AND ABANDONMENT PLAN**

**Submit a plan for plugging and abandonment of the well. Submit this information on EPA Form 7520-14, Plugging and Abandonment Plan.**

Attachment Q-1	EPA Form 7520-14, Plugging and Abandonment Plan
Attachment Q-2	Wellbore Schematic of Proposed Plugging and Abandonment
Attachment Q-3	Work Procedure for Plugging and Abandonment



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

WASHINGTON, DC 20460

## PLUGGING AND ABANDONMENT PLAN

NAME AND ADDRESS OF FACILITY  
Tar Sands Federal #15-28-8-17  
Duchesne County, Utah

NAME AND ADDRESS OF OWNER/OPERATOR  
Inland Production Company  
410 17th Street, Suite 700  
Denver, Colorado 80202

<p>LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT --- 640 ACRES</p>	STATE Utah	COUNTY Duchesne	PERMIT NUMBER 43-013-32109
	SURFACE LOCATION DESCRIPTION ¼ OF SW ¼ OF SE SECTION 28 TOWNSHIP 8S RANGE 17E		
	LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface Location _____ 518 ft. from (N/S) _____ S _____ Line of quarter section and _____ 1890 ft. from (E/W) _____ E _____ Line of quarter section		
	<p>TYPE OF AUTHORIZATION</p> <input checked="" type="checkbox"/> Individual Permit <input type="checkbox"/> Area Permit <input type="checkbox"/> Rule <p>Number of Wells _____ 1</p> <p>Lease Name _____ Tar Sands Federal</p>		<p>WELL ACTIVITY</p> <input type="checkbox"/> CLASS I <input checked="" type="checkbox"/> CLASS II <input type="checkbox"/> Brine Disposal <input checked="" type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage <input type="checkbox"/> CLASS III <p>Well Number _____ #15-28-8-17</p>

## CASING AND TUBING RECORD AFTER PLUGGING

## METHOD OF EMPLACEMENT OF CEMENT PLUGS

SIZE	WT(LB/FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE
8-5/8"	24	311'	311'	12-1/4"
4-1/2"	11.6	6114'	6114'	7-7/8"

- ☒ The Balance Method  
☐ The Dump Bailer Method  
☐ The Two-Plug Method  
☐ Other

CEMENTING TO PLUG AND ABANDON DATA:	PLUG #1	PLUG #2	PLUG #3	PLUG #4	PLUG #5	PLUG #6	PLUG #7
Size of Hole or Pipe in which Plug Will be Placed (inches)	5-1/2"	5-1/2"	5-1/2"	5-1/2"	5-1/2"	annulus	
Depth to Bottom of Tubing or Drill Pipe (ft.)	5987'	5987'	5987'	5987'	5987'	5987'	
Sacks of Cement To Be Used (each plug)	40	90	30	15	10	10	
Slurry Volume To Be Pumped (cu. Ft.)							
Calculated Top of Plug (ft.)	5665'	4569'	2000'	257'	surface	surface	
Measured Top of Plug (if tagged ft.)							
Slurry Wt. (Lb./Gal.)	15.8	15.8	15.8	15.8	15.8	15.8	
Type Cement or Other Material (Class III)	Class G	Class G	Class G	Class G	Class G	Class G	

## LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (if any)

From	To	From	To
no open holes			

Estimated Cost to Plug Wells \$18,000

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print)  
Bill Pennington  
Chief Financial Officer

SIGNATURE

DATE SIGNED

February 28, 2001

## Tar Sands Federal #15-28


Spud Date: 8/10/00  
 Put on Production: 9/19/00  
 GL: 5132' KB: 5142'

SURFACE CASING

CSG SIZE: 8-5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 311' (7 jts)  
 DEPTH LANDED: 307.16' GL  
 HOLE SIZE: 12-1/4"  
 CEMENT DATA: 141 sx Class "G" cement plus additives

PRODUCTION CASING

CSG SIZE: 4-1/2"  
 GRADE: J-55  
 WEIGHT: 11.6#  
 LENGTH: 144 jts (6113.84')  
 DEPTH LANDED: 6109.84'  
 HOLE SIZE: 7-7/8"  
 CEMENT DATA: 360 sx PremLite II, followed by 625 sx 50/50 Pozmix.

Proposed P & A  
Wellbore Diagram

Inland Resources Inc.

Tar Sands Federal #15-28

518 FSL 1890 FEL

SWSE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32109; Lease #U-76241

## ATTACHMENT Q-3

### WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1. Plug #1 Set 329' plug from 5665'-5994' with 40 sxs Class "G" cement.
2. Plug #2 Set 766' plug from 4569'-5335' with 90 sxs Class "G" cement.
3. Plug #3 Set 200' plug from 2000'-2200' with 25 sxs Class "G" cement.
4. Plug #4 Set 100' plug from 257'-357' with 20 sxs Class "G" cement (50' above and 50' below casing shoe).
5. Plug #5 Set 50' plug from surface with 10 sxs Class "G" cement.
6. Plug #6 Pump 10 sxs Class "G" cement down the 8-7/8" x 4-1/2" annulus to cement to surface.

**ATTACHMENT R**  
**NECESSARY RESOURCES**

**Submit evidence such as a surety bond or financial statement to verify that the resources necessary to close, plug, or abandon the well are available.**

Inland Production Company demonstrates financial responsibility by submitting annually the 10K financial report.



## APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR	Inland Production Company
ADDRESS	410 17th Street, Suite 700
	Denver, Colorado 80202

Well Name and number:	Tar Sands Federal #15-28-8-17		
Field or Unit name:	Monument Butte Field	Lease No.	U-76241
Well Location: QQ	SW/SE	section 28	township 8S range 17E county Duchesne
Is this application for expansion of an existing project? . . . . . Yes [ X ] No [ ]			
Will the proposed well be used for:			
	Enhanced Recovery?	Yes [ X ] No [ ]	
	Disposal?	Yes [ ] No [ X ]	
	Storage?	Yes [ ] No [ X ]	
Is this application for a new well to be drilled? . . . . . Yes [ ] No [ X ]			
If this application is for an existing well,			
has a casing test been performed on the well? . . . . . Yes [ ] No [ X ]			
Date of test: Will be done at time of conversion			
API number: 43-013-32109			
Proposed injection interval: from 4969' to 5944'			
Proposed maximum injection: rate 500 bpd pressure 1563 psig			
Proposed injection zone contains [ X ] oil, [ ] gas, and/or [ ] fresh water within 1/2 mile of the well.			
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.			
List of Attachments: Attachments A through R			
I certify that this report is true and complete to the best of my knowledge.			
Name:	Bill Pennington	Signature	Bill Pennington
Title	Chief Financial Officer	Date	February 28, 2001
Phone No.	(303) 893-0102		
(State use only)			
Application approved by		Title	
Approval Date			

Comments:

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS, AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT -" for such proposals

*SUBMIT IN TRIPLICATE*

1. Type of Well



Oil Well



Gas well



Other

2. Name of Operator

**INLAND PRODUCTION COMPANY**

3. Address and Telephone No.

**410 Seventeenth Street, Suite 700 Denver, CO 80202 (303) 893-0102**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SW/SE

518' FSL, 1890' FEL

Sec. 28, T8S, R17E

5. Lease Designation and Serial No.

U-76241

6. If Indian, Allottee or Tribe Name

NA

7. If unit or CA, Agreement Designation

8. Well Name and No.

Tar Sands Fed #15-28

9. API Well No.

43-013-32109

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne County, UT

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION



Notice of Intent



Abandonment



Change of Plans



Subsequent Report



Recompletion



New Construction



Final Abandonment Notice



Plugging Back



Non-Routine Fracturing



Casing repair



Water Shut-off



Altering Casing



Conversion to Injection



Other \_\_\_\_\_



Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directly drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

Please see attached injection application.

**RECEIVED**

MAR 28 2001

**DIVISION OF  
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct

Signed

*Joyce I. McGough*  
**Joyce I. McGough**

Title

**Regulatory Specialist**

Date

**2/28/01**

(This space of Federal or State office use.)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly to make to any department of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor

Kathleen Clarke  
Executive Director

Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

April 24, 2001

Inland Production Company  
410 Seventeenth Street, Suite 700  
Denver, Colorado 80202

Re: Greater Boundary Unit Well: Tar Sands Federal 15-28-8-17, Section 28, Township 8 South, Range 17 East, Duchesne County, Utah

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Inland Production Company.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.

If you have any questions regarding this approval or the necessary requirements, please contact Brad Hill or Dan Jarvis at this office.

Sincerely,

A handwritten signature in black ink, appearing to read 'John R. Baza'.

John R. Baza  
Associate Director

cc: Dan Jackson, Environmental Protection Agency  
Bureau of Land Management, Vernal  
Inland Production Company, Myton

DIVISION OF OIL, GAS AND MINING  
UNDERGROUND INJECTION CONTROL PROGRAM

**PERMIT  
STATEMENT OF BASIS**

**Applicant:** Inland Production Company

**Well:** Tar Sands Fed. 15-28-8-17

**Location:** 28/8S/17E

**API:** 43-013-32109

**Ownership Issues:** The proposed well is located on BLM land. The well is located in the Greater Boundary Unit. Lands in the one-half mile radius of the well are administered by the BLM. The Federal Government is the mineral owner within the area of review. Inland and other various individuals hold the leases in the unit. Inland has provided a list of all surface, mineral and lease holders in the half-mile radius. Inland will be the operator of the Greater Boundary Unit. Inland has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

**Well Integrity:** The proposed well has surface casing set at 311 feet and has a cement top at the surface. A 5 ½ inch production casing is set at 6110 feet and has a cement top at 466'. A cement bond log verifies adequate bond well above the injection zone. A 2 7/8 inch tubing with a packer will be set at 4936 feet. A mechanical integrity test will be run on the well prior to injection. There are 7 producing wells and 3 water injection wells in the area of review. All of the wells have adequate casing and cement. No corrective action will be required.

**Ground Water Protection:** According to Technical Publication No. 92 the base of moderately saline water is at a depth of approximately 150 feet. Injection shall be limited to the interval between 4969 feet and 5944 feet in the Green River Formation. Information submitted by Inland indicates that the fracture gradient for the 15-28-8-17 well is .706 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 1563 psig. The requested maximum pressure is 1563 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

**Oil/Gas& Other Mineral Resources Protection:** The Board of Oil, Gas & Mining approved the Greater Boundary Unit on August 24, 1992 and revised it on April 4, 1998. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

**Bonding:** Bonded with the BLM


**Actions Taken and Further Approvals Needed:** A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that Administrative approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Brad Hill

Date 4/24/2001


● MIC-271 ●



# AFFIDAVIT OF PUBLICATION

County of Duchesne,  
STATE OF UTAH

I, Craig L. Ashby on oath, say that I am the PUBLISHER of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for 1 consecutive issues, and that the first publication was on the 10 day of April, 20 01, and that the last publication of such notice was in the issue of such newspaper dated the 10 day of April, 20 01.

  
\_\_\_\_\_  
Publisher

Subscribed and sworn to before me this

12 day of April, 20 01

  
\_\_\_\_\_  
Notary Public

## NOTICE OF AGENCY ACTION

CAUSE NO. UIC-271  
BEFORE THE DIVI-  
SION OF OIL, GAS AND  
MINING, DEPART-  
MENT OF NATURAL  
RESOURCES, STATE OF  
UTAH.

IN THE MATTER OF  
THE APPLICATION OF  
INLAND PRODUCTION  
COMPANY FOR AD-  
MINISTRATIVE AP-  
PROVAL OF THE TAR  
SANDS FEDERAL 11-28-  
8-17 AND 15-28-8-17  
WELLS LOCATED IN  
SECTION 28, TOWNSHIP  
8 SOUTH, RANGE 17  
EAST, S.L.M.,  
DUCESNE COUNTY,  
UTAH, AS A CLASS II  
INJECTION WELLS.

THE STATE OF UTAH  
TO ALL PERSONS IN-  
TERESTED IN THE  
ABOVE ENTITLED  
MATTER.

Notice is hereby given  
that the Division of Oil, Gas  
and Mining (the "Division")  
is commencing an informal  
adjudicative proceeding to  
consider the application of  
Inland Production Company  
for administrative approval  
of the Tar Sands Federal 11-  
28-8-17 and 15-28-8-17  
wells, located in Section 28,  
Township 8 South, Range  
17 East, Duchesne County,  
Utah, for conversion to  
Class II injection wells. The  
proceeding will be conducted  
in accordance with Utah  
Admin. R649-10, Adminis-  
trative Procedures.

Selective zones in the  
Green River Formation will  
be used for water injection.  
The maximum requested  
injection pressure and rate  
will be determined based on  
fracture gradient information  
submitted by Inland Pro-  
duction Company.

Any person desiring to  
object to the application or  
otherwise intervene in the  
proceeding must file a writ-  
ten protest or notice of in-  
tervention with the Divi-  
sion within fifteen days fol-  
lowing the date of this

Notary Public

Any person desiring to object to the application or otherwise intervene in the proceeding must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 2<sup>nd</sup> day of April, 2001.

STATE OF UTAH  
DIVISION OF OIL,  
GAS & MINING

John R. Baza

Associate Director

Published in the Uintah  
Basin Standard April 10,  
2001.



143 SOUTH MAIN ST.  
P.O. BOX 45838  
SALT LAKE CITY, UTAH 84145  
FED. TAX I.D.# 87-0217663

# Newspaper Agency Corporation

The Salt Lake Tribune



DESERET NEWS

CUSTOMER'S  
COPY

## PROOF OF PUBLICATION

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	DATE
DIV OF OIL-GAS & MINING 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114	D5385340L-07	04/09/01

ACCOUNT NAME	
DIV OF OIL-GAS & MINING	
TELEPHONE	INVOICE NUMBER
801-538-5340	TL82013S3E1
SCHEDULE	
START 04/09/01 END 04/09/01	
CUST. REF. NO.	
UIC-271	
CAPTION	
BEFORE THE DIVISION OF OIL, GA	
SIZE	
57 LINES 2.00 COLUMN	
TIMES	RATE
1	1.16
MISC. CHARGES	AD CHARGES
.00	132.24
TOTAL COST	
132.24	

### AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKKEEPER, I CERTIFY THAT  
ADVERTISEMENT OF BEFORE THE DIVISION OF OIL, GA  
DIV OF OIL-GAS & MINING WAS PUBLISHED BY THE NEW  
CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DA  
PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH  
IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH.

PUBLISHED ON START 04/09/01 END 04/09/01

SIGNATURE *Patricia Hony*

DATE 04/09/01

**THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"**  
**PLEASE PAY FROM BILLING STATEMENT.**

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH

---ooOoo---

IN THE MATTER OF THE  
APPLICATION OF INLAND  
PRODUCTION COMPANY FOR  
ADMINISTRATIVE APPROVAL OF  
THE TAR SANDS FEDERAL 11-28-  
8-17 AND 15-28-8-17 WELLS  
LOCATED IN SECTION 28, TOWNSHIP 8 SOUTH,  
SHIP 8 SOUTH, RANGE 17 EAST,  
S.L.M. DUCHESNE COUNTY, UTAH, :  
AS A CLASS II INJECTION WELLS

: NOTICE OF AGENCY  
ACTION  
: CAUSE NO. UIC-271

---ooOoo---

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE  
ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas  
and Mining (the "Division") is commencing an informal  
adjudicative proceeding to consider the application of  
Inland Production Company for administrative approval  
of the Tar Sands Federal 11-28-8-17 and 15-28-8-17  
Wells, located in Section 28, Township 8 South, Range  
17 East, Duchesne County, Utah, for conversion to a Class  
II injection wells. The proceeding will be conducted in  
accordance with Utah Admin. R649-10, Administrative  
Procedures.

Selective zones in the Green River Formation will be  
used for water injection. The maximum requested injection  
pressure and rate will be determined based on  
fracture gradient information submitted by Inland Pro-  
duction Company.

Any person desiring to object to the application or  
otherwise intervene in the proceeding, must file a written  
protest or notice of intervention with the Division within  
fifteen days following publication of this notice. If such  
a protest or notice of intervention is received, a hearing  
will be scheduled in accordance with the aforementioned  
administrative procedural rules. Protestants and/or in-  
terveners should be prepared to demonstrate at the  
hearing how this matter affects their interests.

Dated this 2nd day of April, 2001.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING

/s/ John R. Baza  
Associate Director

82013S3E



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8  
999 18<sup>TH</sup> STREET - SUITE 300  
DENVER, CO 80202-2466  
<http://www.epa.gov/region08>

DEC 12 2003

Ref: 8P-W-GW

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**

Mr. Mike Guinn  
Vice President - Operations  
Inland Production Company  
Route 3 - Box 3630  
Myton, UT 84502

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY

RECEIVED

DEC 15 2003

RE: **ADDITIONAL WELL TO BOUNDARY AREA PERMIT**  
TAR SANDS FEDERAL NO. 15-28-8-17  
Well ID No. **UT20702-04625**  
Boundary Area Permit UT20702-00000  
Duchesne County, Utah

DIV. OF OIL, GAS & MINING

Dear Mr. Guinn:

The Inland Production Co. (Inland) request to convert a former Garden Gulch-Douglas Creek Members of the Green River Formation oil well, the Tar Sands Federal No. 15-28-8-17, to a Green River Formation Garden Gulch-Douglas Creek-Basal Carbonate Members enhanced recovery injection well, in the Boundary Area Permit, is hereby authorized. The proposed Tar Sands Federal No. 15-28-8-17 Class II enhanced recovery injection well is within the exterior boundary of Boundary Area Permit UT20702-00000; is within the exterior boundary of the Uintah & Ouray Indian Reservation; and the addition is being made under the authority of 40 CFR § 144.33 (c), and the terms of the Boundary Area Permit. Unless specifically mentioned in the enclosed Authorization For An Additional Well, all terms and conditions of the original Boundary Area Permit will apply to the conversion, operation, monitoring, and plugging of the Tar Sands Federal No. 15-28-8-17.

Prior to beginning injection, the Environmental Protection Agency (EPA) requires that Inland submit for review and approval (1) the results of a Part I (Internal) Mechanical Integrity Test (MIT), (2) a pore pressure calculation of the injection interval, and (3) an EPA Form No. 7520-12 (Well Rework Record, enclosed).



Printed on Recycled Paper

Pursuant to Part II. Section C. Condition No. 4, (Injection Pressure Limitation), Boundary Area Permit UT20702-00000, the initial surface injection pressure shall not exceed 1800 psig, **but the initial maximum surface injection pressure of the Tar Sands Federal No. 15-28-8-17 shall not exceed 1345 psig.** The Boundary Final Area Permit, Part II. C. 4., provides an opportunity for the permittee to request an increase, or decrease, in the initial maximum surface injection pressure.

Please be aware that Inland does not have authorization to begin injection into the Tar Sands Federal No. 15-28-8-17 until the Prior to Commencing Injection requirements, listed above, have been submitted and evaluated by the EPA, and Inland has received written authorization to begin injection from the Assistant Regional Administrator, or the Assistant Regional Administrator's authorized representative.

If Inland Production Company has any questions, please call Dan Jackson at (303) 312-6155 if in the Denver area, or 1.800.227.8917 (Ext. 6155) if calling from outside the Denver area. Please submit the required pre-authorization to inject data to the **ATTENTION: Dan Jackson**, at the letterhead address, citing **MAIL CODE: 8P-W-GW** very prominently.

Sincerely,

*Carl S. Campbell for*

Stephen S. Tuber  
Assistant Regional Administrator  
Office of Partnerships and  
Regulatory Assistance

enclosures: Authorization For An Additional Well  
Form No. 7520-12 (Well Rework Record)

cc w/enclosures: Ms. Maxine Natchees  
Chairwoman  
Uintah & Ouray Business Committee  
Ute Indian Tribe  
P.O. Box 190  
Fort Duchesne, UT 84026

Ms. Elaine Willie  
Environmental Director  
Ute Indian Tribe  
P.O. Box 460  
Fort Duchesne, UT 84026

Mr. Chester Mills  
Superintendent  
Bureau of Indian Affairs  
Uintah & Ouray Indian Agency  
P.O. Box 130  
Fort Duchesne, UT 84026

Mr. David Gerbig  
Operations Engineer  
Inland Production Company  
410 Seventeenth Street - Suite 700  
Denver, CO 80202

Mr. Gil Hunt  
Technical Services Manager  
State of Utah - Natural Resources  
Division of Oil, Gas, and Mining  
1594 West North Temple - Suite 1220  
Salt Lake City, UT 84114-5801

Mr. Jerry Kenczka  
Petroleum Engineer  
Bureau of Land Management  
170 South 500 East  
Vernal, UT 84078



## UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8  
999 18<sup>TH</sup> STREET - SUITE 300  
DENVER, CO 80202-2466  
Phone 800-227-8917  
<http://www.epa.gov/region08>

### AUTHORIZATION FOR AN ADDITIONAL WELL TO THE BOUNDARY AREA PERMIT: UT20702-00000

The Environmental Protection Agency (EPA) authorizes the inclusion of an additional enhanced recovery injection well to the Boundary Area Permit No. UT20702-00000, as authorized by 40 CFR § 144.33 (c). The additional well is described as:

**WELL NAME: TAR SANDS FEDERAL NO. 15-28-8-17**

**WELL PERMIT NUMBER: UT20702-04625**

**SURFACE LOCATION:** 518' FSL & 1890' FEL (SW SE)  
Sec. 28 - T8S - R17E  
Duchesne County, Utah.

This well is subject to all provisions of the original Area Permit (UT20702-00000), and subsequent Modifications, unless specifically detailed below.

**POSTPONEMENT OF CONVERSION:** If the Tar Sands Federal No. 15-28-8-17 (TSF No. 15-28) is not converted/completed for enhanced recovery within one (1) year from the effective date of this AUTHORIZATION FOR AN ADDITIONAL WELL TO THE BOUNDARY AREA PERMIT, the TSF No. 15-28 will be plugged and abandoned in accordance with the Plugging and Abandonment Plan as described in APPENDIX C of this document, **unless the permittee requests an extension.** The written request shall be made to the Director, and shall state the reasons for the delay in conversion/construction, and the permittee will confirm that all underground sources of drinking water (USDW) will be protected. **The extension under POSTPONEMENT OF CONVERSION may not exceed one (1) year.**

**UNDERGROUND SOURCE OF DRINKING WATER (USDW):** The base of the Uinta Formation USDW in the TSF No. 15-28 occurs approximately **132 feet** from the surface. The source for the location of the base of the Uinta Formation USDW is the STATE OF UTAH: PUBLICATION NO. 2. BASE OF MODERATELY SALINE GROUND WATER IN THE UINTA BASIN, UTAH. Surface casing was set at **307 feet** and cemented to the surface.



Documentation submitted with the application for a Boundary Area Permit, and this application for an Additional Well to the Area Permit, identify the total dissolved solids (TDS) of the produced Garden Gulch/Douglas Creek/Basal Carbonate Members water as approximately **15,646 mg/l**. The injectate is produced water blended with source water from the Johnson Water District reservoir (TDS: **600 mg/l**). The blended injectate has been analyzed at **5704 mg/l TDS**.

#### **UNDERGROUND SOURCES OF DRINKING WATER (USDW) EXEMPTION:**

There are no USDWs within the TSF No. 15-28 Area-of-Review (AOR) that require an Aquifer Exemption.

#### **WATER WELLS AND/OR SPRINGS: ([HTTP://NRWRT1.NR.STATE.UT.US/](http://nrwrt1.nr.state.ut.us/))**

##### **RE: Water Rights. Queries. POD.**

There are no domestic or agricultural water wells within the AOR of the TSF No. 15-28. There are no springs within this AOR.

#### **CONFINING ZONE REVIEW: TSF No. 15-28**

The EPA identifies the confining zone directly overlying the top of the **Garden Gulch Member** throughout the Boundary Area Permit as a 26-foot to 160-foot shale zone. Depths to the top of the Garden Gulch confining interval vary from 4218 feet in the north to 3998 feet in the south. **The equivalent Garden Gulch Member confining zone thickness in the TSF No. 15-28 is twenty-six (26) feet, i.e., 3934 feet to 3908 feet.**

An EPA analysis of the TSF No. 15-28 CBL/GR identifies the uppermost continuous 80% bond index cement bond from **4034 feet to 4197 feet**; a thickness of 163 feet. **There is no continuous 80% cement bond above and/or across the Garden Gulch confining zone (3908 feet to 3934 feet)**, pursuant to standards of Region 8 GROUND WATER SECTION GUIDANCE NO. 34 Cement Bond Logging Techniques and Interpretation. Therefore, it **has not been determined** that the cement in this well provides an effective barrier to significant upward movement of fluids through vertical channels adjacent to the wellbore (Part II Mechanical Integrity [MI]), pursuant to 40 CFR § 146.8 (a) (2). **The permittee will be required to demonstrate Part II External MI** (Ground Water Section Guidance No. 37: Demonstrating Part II Mechanical Integrity for a Class II Injection Well) within 180 days following receipt of the Director's authority to commence injection..

### **INJECTION ZONE REVIEW: TAR SANDS FEDERAL NO. 15-28-8-17**

The top of the Garden Gulch Member is 3934 feet. The authorized injection zone for the Tar Sands Federal No. 15-28-8-17 runs from 3934 feet to the top of the Wasatch Formation (Estimated at 6285 feet).

By a Major Boundary Area Permit Modification No. 3, effective May 19, 2003, the gross enhanced recovery injection interval was authorized to include the Garden Gulch-Douglas Creek-Basal Carbonate Members of the Green River Formation. Within the Boundary Area Permit, tops of the Garden Gulch-Douglas Creek-Basal Carbonate Members in all Class II injection wells were to be based on correlation to the TYPE LOG, Federal No. 1-26, NE NW Section 26 - T8S-R17E, Duchesne County, Utah (UT20702-04671).

### **WELL CONSTRUCTION REVIEW: TAR SANDS FEDERAL NO. 15-28-8-17**

**SURFACE CASING:** 8-5/8 inch casing is set at 307 feet ground level (GL) in a 12-1/4 inch hole using 141 sacks of Class "G" cement circulated to the surface. The Uinta Formation underground sources of drinking water (USDWs) are at a maximum 132 feet from the surface. Annulus cement and depth of surface casing are considered adequate to protect USDWs in this well.

**LONGSTRING CASING:** 5-1/2 inch casing is set at 6110 feet KB with 360 sacks of PremLite mixed with 625 sacks of 50/50 Pozmix. The EPA analysis of the CBL/GR shows the top interval of 80% cement bond index annulus cement as 4034 feet to 4197 feet (163 feet).

## **PART II. A. CONSTRUCTION REQUIREMENTS FOR ADDITIONAL WELLS**

### **Tubing and Packer Specifications:**

(Condition 3)

For injection purposes, the **TSF No. 15-28** will be equipped with 2-7/8 tubing with a packer to be set at a depth no higher than 100 feet above the top perforation.

### **Formation Testing and Logging**

(Condition 6)

- (a) Upon conversion of the **TSF No. 15-28**, the permittee is required to determine the injection zone **fluid pore pressure** (static bottom hole pressure) prior to commencement of enhanced recovery injection operation. The results of this test shall be submitted to the EPA.

- (b) A **step-rate test (SRT)** shall be performed on the **TSF No. 15-28** within three (3) to six (6) months after injection operations were initiated. The results shall be submitted to the EPA. The permittee will contact the EPA prior to conducting the SRT to acquire the most current Guidance for conducting the SRT.

## **PART II. B. CORRECTIVE ACTION**

As of November 2003, there are (1) Class II enhanced recovery injection well (UT20702-04514), three (3) Douglas Creek Member oil wells, and one (1) Garden Gulch/Douglas Creek Members oil well within the one-quarter (1/4) mile area-of-review (AOR). There are no staked/undrilled locations within the AOR.

**TAR SANDS FEDERAL NO. 1-33-8-17: UT20702-04514 (NE NE Sec. 33-T8S-R17E)**. Authorized for Conversion to a Garden Gulch/Douglas Creek/Basal Carbonate Members of the Green River Formation enhanced recovery injection well on March 1, 2000. Limited Authorization to Inject for 180 days on September 6, 2001. Authorized to continue injection after review and approval of Part II Mechanical Integrity (Radioactive Tracer Survey).

### **DOUGLAS CREEK MEMBER OIL WELLS:**

**Tar Sands Federal No. 2-33-8-17** (NW NE Sec. 33-T8S-R17E)  
The EPA compared the confining interval, overlying the top of the Garden Gulch Member, to the top of the 80% bond index cement bond, and the EPA has concluded that there is no EPA-acceptable annulus cement across the Garden Gulch confining interval. Therefore, pursuant to Part II. B., Boundary Area Permit, the permittee is required to monitor the **TSF No. 2-33** at least **once weekly** for indications of fluid at the surface behind longstring casing, or other indications of leakage. If any such leakage is discovered at the **TSF No. 2-33** injection into the **TSF No. 15-28** shall be halted immediately, and the Director notified pursuant to Part III, Sec. E. 10. of the Boundary Area Permit.

**Tar Sands Federal No. 14-28-8-17** (SE SW Sec. 28-T8S-R17E)  
The EPA compared the confining interval, overlying the top of the Garden Gulch Member, to the top of the 80% bond index cement bond, and the EPA has concluded that there is no EPA-acceptable annulus cement across the Garden Gulch confining interval. Therefore, pursuant to Part II. B., Boundary Area Permit, the permittee is required to monitor the **TSF No. 14-28** at least **once weekly** for indications of fluid at the surface behind longstring casing, or other indications of leakage. If any such leakage is discovered at the **TSF No. 14-28** injection into the **TSF No. 15-28** shall be halted immediately, and the Director notified pursuant to Part III, Sec. E. 10. of the Boundary Area Permit.



**Tar Sands Federal No. 16-28-8-17** (SE SE Sec. 28-T8S-R17E)

The EPA compared the confining interval, overlying the top of the Garden Gulch Member, to the top of the 80% bond index cement bond, and the EPA has concluded that there is no EPA-acceptable annulus cement across the Garden Gulch confining interval. Therefore, pursuant to Part II. B., Boundary Area Permit, the permittee is required to monitor the **TSF No. 16-28** at least **once weekly** for indications of fluid at the surface behind longstring casing, or other indications of leakage. If any such leakage is discovered at the **TSF No. 16-28** injection into the **TSF No. 15-28** shall be halted immediately, and the Director notified pursuant to Part III. Sec. E. 10. of the Boundary Area Permit.

**GARDEN GULCH/DOUGLAS CREEK MEMBERS OIL WELL:****Tar Sands Federal No. 10-28-8-17** (NW SE Sec. 28-T8S-R17E)

The EPA compared the confining interval, overlying the top of the Garden Gulch Member, to the top of the 80% bond index cement bond, and the EPA has concluded that there is no EPA-acceptable annulus cement across the Garden Gulch confining interval. Therefore, pursuant to Part II. B., Boundary Area Permit, the permittee is required to monitor the **TSF No. 10-28** at least **once weekly** for indications of fluid at the surface behind longstring casing, or other indications of leakage. If any such leakage is discovered at the **TSF No. 10-28** injection into the **TSF No. 15-28** shall be halted immediately, and the Director notified pursuant to Part III. Sec. E. 10. of the Boundary Area Permit.

**PART II. C. WELL OPERATION****Prior to Commencing Injection (Additional Wells)**

(Condition 2)

**Tar Sands Federal No. 15-28-8-17:** This document is being issued without authority to inject. Prior to beginning injection, the operator is required to submit the following information for EPA review and written approval:

- (1) A successful **mechanical integrity test (MIT) Part I (Internal)**, as described in **GROUND WATER SECTION GUIDANCE NO. 39**;
- (2) a **pore pressure calculation** of the proposed injection zone; and
- (3) an EPA Form No. 7520-12 (**Well Rework Record**, enclosed).

Part II (External) MI is required within the 180-day limited authorization period.

Injection Interval

(Condition 3)

Injection shall be limited to the **gross Garden Gulch-Douglas Creek-Basal Carbonate Members of the Green River Formation**, 3934 feet (KB) to the top of the Wasatch Formation at an approximate depth of 6285 feet (KB).

Injection Pressure Limitation

(Condition 4)

Pursuant to Final Area Permit UT20702-00000, Part II. Section C. 4. (b). the maximum surface injection pressure (MIP) shall not exceed 1800 psig. Until such time that a step-rate injectivity test (SRT) has been performed, reviewed, and approved by the EPA, the initial maximum surface injection pressure (MIP) for the Tar Sands Federal No. 15-28-8-17 shall not exceed **1345 psig**.

FG	=	0.706 (This Sand/Frac FG value is consistent with other Sec. 28 Sand/Frac or SRT FG values)
D	=	4969 (Depth to top perforation)
SG	=	1.005
0.433	=	Density fresh water
MIP	=	$[0.706 - (0.433)(1.005)] 4969 = 1346 \text{ psig}$ , but reduced to 1345 psig.

Final Area Permit (UT20702-00000), has a provision whereby the operator may request an increase, or decrease, in the maximum surface injection pressure.

**PART II. F. FINANCIAL RESPONSIBILITY**Demonstration of Financial Responsibility (FRD)

(Condition 1)

The applicant has chosen to demonstrate financial responsibility for the Tar Sands Federal No. 15-28-8-17 within a \$15,000 Schedule A of the Standby Trust Agreement. This document was reviewed and approved by the EPA.

**APPENDIX C**

PLUGGING AND ABANDONMENT: The Plugging and Abandonment (P&A) Plan (Application Attachment Q-2) submitted by the applicant has been reviewed and approved with a modification, by the EPA, of Plug No. 5. The P&A Plan, as modified, is consistent with EPA requirements to protect all USDWs. The permittee will place 9.2 ppg plugging gel or bentonite mud between all cement plugs.

PLUG NO. 1: Set a cement plug inside of the 5-1/2 inch casing from 5665 feet to 5944 feet.

PLUG NO. 2: Set a cement plug inside of the 5-1/2 inch casing from 4569 feet to 5335 feet.

PLUG NO. 3: Set a cement plug inside of the 5-1/2 inch casing from 2000 feet to 2200 feet.

PLUG NO. 4: Set a cement plug inside of the 5-1/2 inch casing, from 257 feet to 357 feet.

PLUG NO. 5: Set a cement plug, on the backside of the 5-1/2 inch casing, from surface to a depth of 357 feet.

PLUG NO. 6: Set a cement plug, inside of the 5-1/2 inch casing, from the surface to a depth of 50 feet.

This authorization for well conversion only of the Tar Sands Federal No. 15-28-8-17 to an enhanced recovery injection well becomes effective upon signature.

Date: DEC 12 2003

Carl L. Campbell for

(\*) Stephen S. Tuber  
Assistant Regional Administrator  
Office of Partnerships and Regulatory Assistance

(\*) The person holding this title is referred to as the "Director" throughout this Authorization for an Additional Well to the Boundary Area Permit.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

## WELL REWORK RECORD

NAME AND ADDRESS OF PERMITTEE

NAME AND ADDRESS OF CONTRACTOR

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

N									
S									

W E

STATE

COUNTY

PERMIT NUMBER

SURFACE LOCATION DESCRIPTION

1/4 of 1/4 of 1/4 of 1/4 of Section Township Range

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface  
Location ft. from (N/S) Line of quarter section

and ft. from (E/W) Line of quarter section

## WELL ACTIVITY

- ☐ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

Lease Name

Total Depth Before Rework

Total Depth After Rework

Date Rework Commenced

Date Rework Completed

## TYPE OF PERMIT

- ☐ Individual  
☐ Area  
 Number of Wells

Well Number

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

DESCRIBE REWORK OPERATIONS IN DETAIL  
USE ADDITIONAL SHEETS IF NECESSARY

## WIRE LINE LOGS, LIST EACH TYPE

Log Types	Logged Intervals

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

SIGNATURE

DATE SIGNED

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU77098X GRTR BNDRY
2. NAME OF OPERATOR: Inland Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GREATER BOUNDARY
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 517 FSL 1898 FEL		8. WELL NAME and NUMBER: TAR SANDS FED 15-28-8-17
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SW/SE, 28, T8S, R17E		9. API NUMBER: 4301332109
COUNTY: Duchesne		10. FIELD AND POOL, OR WILDCAT: Monument Butte
STATE: Utah		

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will  _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of Work Completion:  12/29/2003			

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS.** Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well was converted from a producing to an injection well on 12/20/03. The rods and tubing anchor were removed and a packer was inserted in bottom hole assembly 4890'. On 12/22/03 Mr. Dan Jackson w/EPA was notified of the intent to conduct a MIT on the casing. On 12/24/03 the casing was pressured to 1495 psi w/ no pressure loss charted in the 1/2 hour test. No governmental agencies were able to witness the test

**Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY**

NAME (PLEASE PRINT) Krishna Russell

TITLE Production Clerk

SIGNATURE

DATE December 29, 2003

(This space for State use only)

**DEC 30 2003**  
DIV. OF OIL, GAS & MINING

# Mechanical Integrity Test

## Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Direct Implementation Program 8P-W-GW  
999 18<sup>th</sup> Street, Suite 500 Denver, CO 80202-2466

EPA Witness: \_\_\_\_\_ Date: 12 / 24 / 03  
Test conducted by: BRET HENZIE  
Others present: \_\_\_\_\_

Well Name: <u>TAR SANDS FEDERAL 15-28-8-17</u>	Type: <u>ER SWD</u>	Status: <u>AC TA UC</u>
Field: <u>GREATER BOUNDARY UNIT</u>		
Location: <u>SW/SE</u> Sec: <u>28</u> T <u>8</u> N/S R <u>17</u> E/W County: <u>DUCHESSNE</u> State: <u>WY</u>		
Operator: <u>INLAND</u>		
Last MIT: <u>- / NA / -</u> Maximum Allowable Pressure: _____ PSIG		

Is this a regularly scheduled test? ☐ Yes ☒ No

Initial test for permit? ☒ Yes ☐ No

Test after well rework? ☐ Yes ☒ No

Well injecting during test? ☐ Yes ☒ No If Yes, rate: \_\_\_\_\_ bpd

Pre-test casing/tubing annulus pressure: 0 psig

MIT DATA TABLE		Test #1	Test #2	Test #3
<b>TUBING PRESSURE</b>				
Initial Pressure	<u>1450</u> psig		psig	psig
End of test pressure	<u>150</u> psig		psig	psig
<b>CASING / TUBING ANNULUS PRESSURE</b>				
0 minutes	<u>1495</u> psig		psig	psig
5 minutes	<u>1495</u> psig		psig	psig
10 minutes	<u>1495</u> psig		psig	psig
15 minutes	<u>1495</u> psig		psig	psig
20 minutes	<u>1495</u> psig		psig	psig
25 minutes	<u>1495</u> psig		psig	psig
30 minutes	<u>1495</u> psig		psig	psig
minutes	psig		psig	psig
minutes	psig		psig	psig
<b>RESULT</b>	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

## MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

This image shows a single sheet of white paper with horizontal blue or grey ruling lines. The lines are evenly spaced and run across the width of the page. There is no handwriting or printed text on the paper.

API # - 43.013.32109

Signature of Witness: \_\_\_\_\_

OFFICE USE ONLY - COMPLIANCE FOLLOWUP

Staff: \_\_\_\_\_ Date: \_\_\_\_/\_\_\_\_/\_\_\_\_

Do you agree with the reported test results?     ☐ YES     ☐ NO

If not, why? \_\_\_\_\_

Possible violation identified? ☐ YES ☐ NO

If YES, what \_\_\_\_\_

If YES - followup initiated? ☐ YES


☐ NO - why not? \_\_\_\_\_

[ ] Data Entry

☐ Compliance Staff

[ ] 2<sup>nd</sup> Data Entry

☐ Hardcopy Filing



TAR SANDS FEDERAL  
15-28-8-17  
GREATER BOUNDARY  
UNIT

WELL NUMBER  
DESCRIPTION  
9:00 AM  
DATE/TIME  
12/24 2003



WELL DEPTH  
TEST PERIOD  
9:30 AM  
DATE/TIME  
12/24 2003

WELL DEPTH  
H2600 W100

SIGNED *End*





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8  
999 18<sup>TH</sup> STREET - SUITE 300  
DENVER, CO 80202-2466  
<http://www.epa.gov/region08>

Ref: 8P-W-GW

JAN 22 2004

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. David Gerbig  
Operations Engineer  
Inland Production Company  
410 Seventeenth Street - Suite 700  
Denver, CO 80202

RE: **180-Day Limited Authorization to Inject**  
Tar Sands Federal No. 15-28-8-17  
EPA Well Permit No. UT20702-04625  
SW SE Sec. 25 - T8S - R17E  
Duchesne County, Utah

Dear Mr. Gerbig:

The December 29, 2003 Inland Production Company (Inland) submission of **Prior to Commencing Injection** documents did contain all information required to fulfill the Environmental Protection Agency's (EPA) **Prior to Commencing Injection** requirements, as stated in the **Authorization for an Additional Well to the Boundary Area Permit (UT20702-04625: Part II, Section C. Condition 2)**. The submitted data included an EPA Well Rework Form (Form No. 7520-12), a Part I (Internal) Mechanical Integrity Test, and the injection zone pore pressure. All data was reviewed and approved by the EPA on January 5, 2004.

The EPA is hereby **authorizing injection into the Tar Sands Federal No. 15-28-8-17 for a limited period of up to one hundred and eighty (180) calendar days effective upon receipt of this letter**, herein referred to as the **"Limited Authorized Period"**.

Because the cement bond log submitted for this well did not show any cement across the confining zone overlying the Garden Gulch Member, **the operator is required to demonstrate Part II (External) Mechanical Integrity (Part II MI) within the 180-day "Limited Authorized Injection Period"**. Approved tests for demonstrating Part II (External) MI include a Temperature Log, a Noise Log, an Oxygen Activation Log, and Region 8 may also accept results of a Radioactive Tracer Survey under certain circumstances. The "Limited Authorized Injection Period" allows injection for the purpose of stabilizing the injection formation pressure prior to demonstrating Part II (External) MI, which is necessary because the proposed injection zone is under-pressured due to previous oil production from the zone, and tests rely on stable formation pressure. Results of any Part II (External) MI Test shall be submitted to Mr. Jackson. Upon



review and approval of the Part II (External) MI Test, the Director will authorize, by letter, continuation of injection into the Tar Sands Federal No. 15-28-8-17.

Copies of Region 8 Guidelines for conducting Part II (External) Mechanical Integrity Tests are enclosed with this letter.

An initial maximum surface injection pressure (MSIP) **not to exceed 1345 psig** was determined for the Tar Sands Federal No. 15-28-8-17 on December 12, 2003. Should the operator apply for an increase to the MSIP at any future date, another demonstration of Part II (External) MI must be conducted in addition to a Step-Rate Test. The operator must receive prior authorization from the Director in order to inject at pressures greater than the permitted MSIP during the test(s).

If you have any questions in regard to the above action, please contact Dan Jackson at 1.800.227.8917 (Ext. 6155). Results from the Temperature Log, or other Part II MI test, should be mailed directly to the **ATTENTION: DAN JACKSON**, at the letterhead address citing **MAIL CODE: 8P-W-GW** very prominently.

Sincerely,



Sandra A. Stavnes  
Director  
Ground Water Program

enclosure: EPA Guideline No. 37: Part II (External) MI  
EPA Guideline for Temperature Logging  
Oxygen Activation Logging  
Radioactive Tracer Survey

cc w/ encl: Mr. Mike Guinn  
Vice President of Operations  
Inland Production Company  
Route 3 - Box 4630  
Myton, UT 84502

cc w/o encl: Ms. Maxine Natchees, Chairwoman  
Uintah & Ouray Business Committee  
Ute Indian Tribe  
P.O. Box 190  
Fort Duchesne, UT 84026

Ms. Elaine Willie  
Environmental Director  
Ute Indian Tribe  
P.O. Box 460  
Fort Duchesne, UT 84026

Mr. Chester Mills  
Superintendent  
Bureau of Indian Affairs  
Uintah & Ouray Indian Agency  
P.O. Box 130  
Fort Duchesne, UT 84026

Mr. Gil Hunt  
Technical Services Manager  
State of Utah - Natural Resources  
Division of Oil, Gas and Mining  
1594 West North Temple - Suite 1220  
Salt Lake City, UT 84111-0581

Mr. Jerry Kenczka  
Petroleum Engineer  
Bureau of Land Management  
Vernal District Office  
170 South 500 East  
Vernal, UT 84078

Mr. Nathan Wiser, 8ENF-UFO

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FOKM APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.  
Use "APPLICATION FOR PERMIT -" for such proposals

5. Lease Designation and Serial No.

**U-76241**

6. If Indian, Allottee or Tribe Name

**NA**

7. If Unit or CA, Agreement Designation

**GREATER BOUNDARY**

8. Well Name and No.

**TAR SANDS FED 15-28-8-17**

9. API Well No.

**43-013-32109**

10. Field and Pool, or Exploratory Area

**MONUMENT BUTTE**

11. County or Parish, State

**DUCHESNE COUNTY, UT**

**SUBMIT IN TRIPLICATE**

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other

2. Name of Operator

**INLAND PRODUCTION COMPANY**

3. Address and Telephone No.

**Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721**

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

**517 FSL 1898 FEL SW/SE Section 28, T8S R17E**

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

**TYPE OF SUBMISSION**

☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

**TYPE OF ACTION**

☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☒ Other **Report of first injection**

☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is direction-ally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

The above referenced well was put on injection at 12:30 p.m. on 1/29/04.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY**

**FEB 02 2004**

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed

*Mandie Crozier*  
**Mandie Crozier**

Title

**Regulatory Specialist**

Date

**1/30/2004**

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> Injection well		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU76241
2. NAME OF OPERATOR: Inland Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GREATER BOUNDARY
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 517 FSL 1898 FEL		8. WELL NAME and NUMBER: TAR SANDS FED 15-28-8-17
5. PHONE NUMBER: 435.646.3721		9. API NUMBER: 4301332109
6. COUNTY: Duchesne		10. FIELD AND POOL, OR WILDCAT: Monument Butte
7. STATE: Utah		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will  _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of Work Completion:  07/15/2004	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Step Rate Test
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


A step rate test was conducted on the subject well on 7/15/04. The fracture pressure was not reached during the test. Therefore, Inland is requesting that the maximum allowable injection pressure (MAIP) be changed to the highest pressure achieved or 1560 psi.

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
**FOR RECORD ONLY**

**RECEIVED**  
**JUL 19 2004**  
DIV. OF OIL, GAS & MINING

NAME (PLEASE) Mike Guinn	TITLE Engineer
SIGNATURE 	DATE July 16, 2004

**Tar Sands Federal 15-28-8-17**  
**Greater Boundary Unit**  
**Step Rate Test**  
**July 15, 2004**



**Start Pressure:**

1150 psi

**Instantaneous Shut In Pressure (ISIP):**

1400 psi

**Top Perforation:**

4969 feet


**Fracture pressure (Pfp):**

N/A psi

**FG:**

N/A psi/ft

Step	Rate(bpd)	Pressure(psi)
1	200	1170
2	400	1210
3	600	1250
4	800	1300
5	1000	1345
6	1200	1390
7	1400	1435
8	1600	1480
9	1800	1520
10	2000	1560





# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155  
<http://www.blm.gov>



IN REPLY REFER TO:  
3106  
(UT-924)

September 16, 2004

### Memorandum

To: Vernal Field Office

From: Acting Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard  
Acting Chief, Branch of  
Fluid Minerals

### Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225  
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114  
Teresa Thompson  
Joe Incardine  
Connie Seare



UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		



## Office of the Secretary of State


The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company  
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT  
TO THE  
ARTICLES OF INCORPORATION  
OF  
INLAND PRODUCTION COMPANY

FILED  
In the Office of the  
Secretary of State of Texas  
SEP 02 2004  
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1<sup>st</sup> day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs  
Susan G. Riggs, Treasurer

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 5

## TRANSFER OF AUTHORITY TO INJECT

Well Name and Number See Attached List		API Number
Location of Well		Field or Unit Name See Attached List
Footage :	County :	Lease Designation and Number
QQ, Section, Township, Range:	State : UTAH	

EFFECTIVE DATE OF TRANSFER: 9/1/2004

## CURRENT OPERATOR

Company: Inland Production Company

Name: Brian Harris

Address: 1401 17th Street Suite 1000

Signature: *Brian Harris*

city Denver state Co zip 80202

Title: Engineering Tech.

Phone: (303) 893-0102

Date: 9/15/2004

Comments:

## NEW OPERATOR

Company: Newfield Production Company

Name: Brian Harris

Address: 1401 17th Street Suite 1000

Signature: *Brian Harris*

city Denver state Co zip 80202

Title: Engineering Tech.

Phone:

Date: 9/15/2004

Comments:

(This space for State use only)

Transfer approved by: *[Signature]*

Approval Date: 9-20-04

Title: *Perk Services Manager*

Comments:

*Note: Indian Country wells will require EPA approval.*RECEIVED  
SEP 20 2004

DIV. OF OIL, GAS &amp; MINING

## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

**X Operator Name Change****Merger**

The operator of the well(s) listed below has changed, effective:

**9/1/2004****FROM: (Old Operator):**

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

**TO: ( New Operator):**

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

**CA No.****Unit:****GREATER BOUNDARY (GR)****WELL(S)**

NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
GBU 3-27-8-17	27	080S	170E	4301332224	12391	Federal	WI	A
GBU 5-27-8-17	27	080S	170E	4301332225	12391	Federal	OW	P
GBU 12-27-8-17	27	080S	170E	4301332226	12391	Federal	OW	P
GBU 1-27-8-17	27	080S	170E	4301332228	12391	Federal	OW	P
GBU 2-27-8-17	27	080S	170E	4301332229	12391	Federal	OW	P
GBU 4-27-8-17	27	080S	170E	4301332230	12391	Federal	OW	P
GBU 6-27-8-17	27	080S	170E	4301332231	12391	Federal	OW	P
GBU 7-27-8-17	27	080S	170E	4301332232	12391	Federal	OW	P
GBU 8-27-8-17	27	080S	170E	4301332233	12391	Federal	OW	P
GBU 9-27-8-17	27	080S	170E	4301332234	12391	Federal	OW	P
GBU 10-27-8-17	27	080S	170E	4301332235	12391	Federal	OW	P
GBU 11-27-8-17	27	080S	170E	4301332243	12391	Federal	OW	P
GBU 13-27-8-17	27	080S	170E	4301332244	12391	Federal	OW	P
GBU 14-27-8-17	27	080S	170E	4301332245	12391	Federal	OW	P
TAR SANDS FED 9-28-8-17	28	080S	170E	4301332067	12391	Federal	WI	A
TAR SANDS FED 8-28-8-17	28	080S	170E	4301332068	12391	Federal	OW	P
TAR SANDS FED 7-28-8-17	28	080S	170E	4301332069	12391	Federal	WI	A
TAR SANDS FED 15-28-8-17	28	080S	170E	4301332109	12391	Federal	WI	A
TAR SANDS FED 16-28-8-17	28	080S	170E	4301332111	12391	Federal	OW	P
GREATER BOUNDARY 11-28-8-17	28	080S	170E	4301332134	12391	Federal	WI	A

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE  
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: UT 0056

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: 61BSBDH2912

**FEE & STATE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
2. The **FORMER** operator has requested a release of liability from their bond on: n/a\*  
The Division sent response by letter on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

**COMMENTS:**

\*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> Injection well		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU76241
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GREATER BOUNDARY II
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 517 FSL 1898 FEL		8. WELL NAME and NUMBER: TAR SANDS FED 15-28-8-17
5. OTR/OTR SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 28, T8S, R17E		9. API NUMBER: 4301332109
6. COUNTY: Duchesne		10. FIELD AND POOL, OR WILDCAT: Monument Butte
7. STATE: Utah		


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	SubDate	TYPE OF ACTION	SubDate
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will  _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE		<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of Work Completion:  05/10/2006			<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARITLY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Step Rate Test	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

A step rate test was conducted on the subject well on April 27, 2006. Results from the test indicate that the fracture gradient is .749 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed to 1560 psi.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY**

NAME (PLEASE PRINT) <u>Cheyenne Batemen</u>	TITLE <u>Well Analyst Foreman</u>
SIGNATURE <u></u>	DATE <u>05/10/2006</u>


(This space for State use only)

RECEIVED

MAY 15 2006

DIV. OF OIL, GAS & MINING


**Tar Sands Federal 15-28-8-17**  
**Greater Boundary II Unit**  
**Step Rate Test**  
**April 27, 2006**



**Start Pressure:** 1290 psi  
**Instantaneous Shut In Pressure (ISIP):** 1565 psi  
**Top Perforation:** 4969 feet  
**Fracture pressure (Pfp):** 1560 psi  
**FG:** 0.749 psi/ft

Step	Rate(bpd)	Pressure(psi)
1	100	1315
2	200	1350
3	300	1390
4	400	1430
5	500	1470
6	600	1510
7	700	1550
8	800	1570
9	900	1590
10	1000	1610





**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:  
USA UTU-76241

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ OTHER

2. NAME OF OPERATOR:  
NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 PHONE NUMBER 435.646.3721

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 517 FSL 1898 FEL

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:  
GREATER BOUNDARY II

8. WELL NAME and NUMBER:  
TAR SANDS FED 15-28-8-17

9. API NUMBER:  
4301332109

10. FIELD AND POOL, OR WILDCAT:  
MONUMENT BUTTE

COUNTY: DUCHESNE

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWSE, 28, T8S, R17E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will  	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of Work Completion:  11/12/2008	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - 5 Year MIT.	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 10/31/08 Nathan Wiser with the EPA was contacted concerning the 5 year MIT on the above listed well. Permission was given at that time to perform the test on 11/15/08. On 11/15/08 the csg was pressured up to 1140 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbg pressure was 1420 psig during the test. There was not an EPA representative available to witness the test.

EPA# UT 20702-04625 API# 43-013-32109

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY

NAME (PLEASE PRINT) Callie Duncan

TITLE Production Clerk

SIGNATURE

DATE 11/14/2008

(This space for State use only)

RECEIVED

NOV 17 2008

DIV. OF OIL, GAS & MINING

# Mechanical Integrity Test

## Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency  
Underground Injection Control Program  
999 18<sup>th</sup> Street, Suite 500 Denver, CO 80202-2466

EPA Witness: \_\_\_\_\_ Date: 11 / 12 / 2008  
Test conducted by: Tim Whithead  
Others present: \_\_\_\_\_

Well Name: <u>TSE 15-28-8-17</u>	Type: ER SWD	Status: AC TA UC
Field: <u>Monument Butte</u>		
Location: <u>SW/SE</u> Sec: <u>28</u> T <u>8</u> N <u>10</u> R <u>17</u> E/W County: <u>Duchenne</u> State: <u>UT</u>		
Operator: <u>Newfield Exploration</u>		
Last MIT: <u>/ /</u>	Maximum Allowable Pressure: <u>1560</u>	PSIG

Is this a regularly scheduled test? ☒ Yes ☐ No  
Initial test for permit? ☐ Yes ☒ No  
Test after well rework? ☐ Yes ☒ No  
Well injecting during test? ☐ Yes ☒ No If Yes, rate: \_\_\_\_\_ bpd

Pre-test casing/tubing annulus pressure: 1420 psig


MIT DATA TABLE	Test #1	Test #2	Test #3
<b>TUBING PRESSURE</b>			
Initial Pressure	<u>1420</u> psig	psig	psig
End of test pressure	<u>1420</u> psig	psig	psig
<b>CASING / TUBING ANNULUS PRESSURE</b>			
0 minutes	<u>1140</u> psig	psig	psig
5 minutes	<u>1140</u> psig	psig	psig
10 minutes	<u>1140</u> psig	psig	psig
15 minutes	<u>1140</u> psig	psig	psig
20 minutes	<u>1140</u> psig	psig	psig
25 minutes	<u>1140</u> psig	psig	psig
30 minutes	<u>1140</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
<b>RESULT</b>	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

## MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: \_\_\_\_\_



43-013-32109



## United States Department of the Interior

### BUREAU OF LAND MANAGEMENT

Utah State Office  
440 West 200 South, Suite 500  
Salt Lake City, UT 84101  
<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO:

3140 / (UT-9223)

UTU-74868, UTU-74869

UTU-74870, UTU-74872

UTU-76241, UTU-77235

APR 09 2013

RECEIVED

APR 11 2013

DIV. OF OIL, GAS & MINING

Tar Sands Fed 15-28-8.17  
8S 17E 28

CERTIFIED MAIL – 7012 3460 0001 4633 6233  
Return Receipt Requested

### DECISION

Newfield Production Company	:	Combined Hydrocarbon Leases
1001 17 <sup>th</sup> Street, Suite 2000	:	UTU-74868 – UTU-74870, UTU-74872
Denver, Colorado 80202	:	UTU-76241 and UTU-77235

### Extension of Time to Comply Granted

Combined Hydrocarbon Leases UTU-74868, UTU-74869, UTU-74870, UTU-74872, UTU-76241 and UTU-77235 were issued to Newfield Production Company (formerly Inland Production Company) effective December 1, 1995, for a period of ten years subject to extension in accordance with the Mineral Lands Leasing Act of February 25, 1920 (30 U.S.C. 181 *et seq.*) and the Combined Hydrocarbon Leasing Act of 1981 (Pub. L. 97-78). Section 4 (b) of the leases state: "Lessee shall diligently develop the tar sand resource in the leased lands as prescribed in the regulations, or as specifically set out by the lessor in approving a plan of operations."

By a notice issued by this office on January 10, 2013, you were requested to submit, within 90 calendar days of the date of receipt of the notice, evidence that a plan of operations was submitted to the Bureau of Land Management (BLM) as required by the regulations.

By a letter dated March 13, 2013, received April 4, 2013, you have requested that an additional 90 day extension (to July 10, 2013) be granted to fully respond to the requirements of the January 10<sup>th</sup> notice. Therefore, by this decision, an extended period of an additional 90 days (until July 10, 2013) is hereby granted to respond to our January 10<sup>th</sup> notice.

If you have any questions concerning this decision, please call Bill Buge of this office at (801) 539-4086.

*Roger L. Bankert*

Roger L. Bankert  
Chief, Branch of Minerals

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-76241
<b>1. TYPE OF WELL</b> Water Injection Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630, Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> TAR SANDS FED 15-28-8-17
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2136 FSL 2199 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSE Section: 28 Township: 08.0S Range: 17.0E Meridian: S		<b>9. API NUMBER:</b> 43013321090000
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>10/17/2013</b>	<input checked="" type="checkbox"/> OTHER		
<input type="checkbox"/> SPUD REPORT Date of Spud:	OTHER: <input style="width: 100px;" type="text" value="5 YR MIT"/>		
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 5 YR MIT performed on the above listed well. On 10/17/2013 the casing was pressured up to 1100 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbp pressure was 1560 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-04625

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 October 24, 2013

<b>NAME (PLEASE PRINT)</b> Lucy Chavez-Naupoto	<b>PHONE NUMBER</b> 435 646-4874	<b>TITLE</b> Water Services Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/21/2013	

# Mechanical Integrity Test

## Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency  
Underground Injection Control Program  
999 18<sup>th</sup> Street, Suite 500 Denver, CO 80202-2466

EPA Witness: \_\_\_\_\_

Date: 10/17/2013Test conducted by: Dustin Bennett

Others present: \_\_\_\_\_

-04625

Well Name: <u>15-28-8-17 Tar Sands</u>	Type: <u>ER SWD</u>	Status: <u>AC TA UC</u>
Field: <u>Monument Butte</u>		
Location: <u>SW/SE</u>	Sec: <u>28 T 8 N</u>	R: <u>17E</u> W: _____ County: <u>Duchesne</u> State: <u>UT</u>
Operator: <u>Newfield Exploration</u>		
Last MIT: <u>1</u>	Maximum Allowable Pressure: <u>1610</u>	PSIG

Is this a regularly scheduled test?

☒ Yes ☐ No

Initial test for permit?

☐ Yes ☒ No

Test after well rework?

☐ Yes ☒ No

Well injecting during test?

☒ Yes ☐ NoIf Yes, rate: 69 bpdPre-test casing/tubing annulus pressure: 1100 / 1560 psig

MIT DATA TABLE	Test #1	Test #2	Test #3
<b>TUBING</b>	<b>PRESSURE</b>		
Initial Pressure	<u>1560</u> psig	psig	psig
End of test pressure	<u>1560</u> psig	psig	psig
<b>CASING / TUBING</b>	<b>ANNULUS PRESSURE</b>		
0 minutes	<u>1100</u> psig	psig	psig
5 minutes	<u>1100</u> psig	psig	psig
10 minutes	<u>1100</u> psig	psig	psig
15 minutes	<u>1100</u> psig	psig	psig
20 minutes	<u>1100</u> psig	psig	psig
25 minutes	<u>1100</u> psig	psig	psig
30 minutes	<u>1100</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
<b>RESULT</b>	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail


Does the annulus pressure build back up after the test? ☐ Yes ☐ No

## MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: \_\_\_\_\_







# Tar Sands Federal #15-28-8-17

Spud Date: 8/10/00

Put on Production: 9/19/00

GL: 5132' KB: 5142'

Initial Production: 115 BOPD,  
75 MCFD, 26 BWPD

## SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 311' (7 jts)

DEPTH LANDED: 307' 16" GL

HOLE SIZE: 12-1/4"

CEMENT DATA: 141 sx Class "G" cement plus additives

## PRODUCTION CASING

CSG SIZE: 4-1/2"

GRADE: J-55

WEIGHT: 11.6#

LENGTH: 144 jts (6113.84')

DEPTH LANDED: 6109.84'

HOLE SIZE: 7-7/8"

CEMENT DATA: 360 sx PremLite II, followed by 625 sx 50/50 Pozmix.

## TUBING

SIZE/GRADE/WT: 2-3/8" / J-55 / 4.7#


NO. OF JOINTS: 149 jts (4872.47')

SN LANDED AT: 4883.57' KB

TUBING PACKER: 4890.17'

TOTAL STRING LENGTH: EOT @ 4890.17' KB

Injection Wellbore  
Diagram



## FRAC JOB

9/14/00 5765'-5944'

**Frac CP sand as follows:**

120,000# 20/40 sand in 721 bbls Viking I-25 fluid. Perfs broke down @ 3550 psi. Treated @ avg press of 2000 psi w/avg rate of 34 BPM. ISIP-1600 psi, 5-min 1495 psi. Left pressure on well.

9/14/00 4969'-5000'

**Frac D-2 sand as follows:**

57,000# 20/40 sand in 356 bbls Viking I-25 fluid. Perfs broke down @ 3980 psi. Treated @ avg press of 2400 psi w/avg rate of 30.5 BPM. ISIP-3100 psi, 5-min 2710 psi. Flowback on 12/64" choke for 2-1/2 hours and died. Rec 77 BTP.

9/14/00 5244'-5285'

**Frac B-2 sand as follows:**

78,000# 20/40 sand in 469 bbls Viking I-25 fluid. Perfs broke down @ 2160 psi. Treated @ avg press of 1800 psi w/avg rate of 30 BPM. ISIP-2030 psi, 5-min 1900 psi. Left pressure on well.

10/19/01

Stuck pump. Update rod and tubing details.

12/20/03

Injection Conversion.

## PERFORATION RECORD

9/14/00	4969'-4978'	4 JSPP	36 holes
9/14/00	4995'-5000'	4 JSPP	20 holes
9/14/00	5244'-5265'	2 JSPP	42 holes
9/14/00	5267'-5285'	2 JSPP	36 holes
9/13/00	5765'-5771'	1 JSPP	6 holes
9/13/00	5791'-5802'	1 JSPP	11 holes
9/13/00	5824'-5828'	1 JSPP	4 holes
9/13/00	5831'-5834'	1 JSPP	3 holes
9/13/00	5921'-5944'	2 JSPP	46 holes



Tar Sands Federal #15-28

518 FSL & 1890 FEL

SWSE Section 28-T8S-R17E

Duchesne Co, Utah

API #43-013-32109; Lease #U-76241

KR 12/29/03